

To download the full report, visit: http://www.undrr.org/gar2023sr

The designations employed and the presentation of the material in this publication do not imply the expression of any opinion whatsoever on the part of the Secretariat of the United Nations concerning the legal status of any country or territory or of its authorities or concerning the delimitations of its frontiers or boundaries. The designations of country groups in the text and the tables are intended solely for statistical or analytical convenience and do not necessarily express a judgment about the stage reached by a particular country or area in the development process. Mention of the names of firms and commercial products does not imply the endorsement of the United Nations.

Some rights reserved. This work is made available under the Creative Commons Attribution-NonCommercial 3.0 IGO licence (CC BY-NC IGO); creativecommons.org/licenses/by-nc/3.0/igo/legalcode

Under the terms of this licence, this work may be copied, redistributed and adapted for non-commercial purposes, provided that the work is appropriately cited. In any use of this work, there should be no suggestion that UNDRR endorses any specific organization, products or services.

The use of the UNDRR logo is not permitted. If a translation of this work is created, it must include the following disclaimer along with the required citation below: "This translation was not created by the United Nations Office for Disaster Risk Reduction (UNDRR). UNDRR is not responsible for the content or accuracy of this translation." UNDRR information products are available for non-commercial use. Requests for commercial use, rights and licensing should be submitted via: www.undrr.org/contact-us

This publication may be freely quoted but acknowledgement of the source is requested.

Citation: United Nations Office for Disaster Risk Reduction (2023). GAR Special Report: Measuring Resilience for the Sustainable Development Goals. Geneva.

ISBN PDF: 9789210028301 ISBN PRINT: 9789213000762

© 2023 UNITED NATIONS OFFICE FOR DISASTER RISK REDUCTION

For additional information, please contact:
United Nations Office for Disaster Risk Reduction (UNDRR)
7bis Avenue de la Paix, CH1211 Geneva 2, Switzerland. Tel: +41 22 917 89 08





GAR Special Report 2023

Mapping Resilience for the Sustainable Development Goals



CONTENTS

Foreword		7
Ac	knowledgements	8
Executive summary		10
1.	Why resilience matters:	12
2.	Understanding risk to people, the planet and prosperity	16
	PEOPLE	19
	Resilience deficit 1. Access to disaster early-warning systems	
	Fully exploiting the potential of early-warning systems	24
	Resilience deficit 2. Increasing drought risk and food insecurity	
	Accelerating the greening of the Sahara through the Great Green Wall initiative	30
	Resilience deficit 3. Forced displacement and negative education outcomes	
	Pre-emptive voluntary relocation of communities to reduce exposure to disasters	34
	PLANET	37
	Resilience deficit 4. Increasing water stress and population growth	
	Transformation within crises	40
	Resilience deficit 5. Increased land degradation and biodiversity loss	42
	Creating a steady state in the governance of natural resources in Cidanau Watershed	44
	Resilience deficit 6. Increased heat stress and energy consumption	46
	Combating heat using a participatory approach	48
	Resilience deficit 7. Increased air pollution and mortality	50
	Leading the way to climate-smart urban planning in Teresina	52

PROSPERITY55 Action case: The European Union Integrating climate risk data into the broader risk management system58 Resilience deficit 9. Increasing heat and poverty......60 Action case: Maldives Action case: Jamaica and Saint Lucia EXTREME SHOCKS AND CASCADING IMPACTS70 3. How to build a more resilient future74 Abbreviations and acronyms90 References 92

FOREWORD

consensus that it would be impossible for developing countries to achieve sustainable development if they were constantly recovering from disasters.

However, in the years since, we have experienced accelerated climate change, unsustainable development choices, growing inequality, poverty and humanitarian needs, that are all increasing the climate change, disaster risk reduction and impacts of disasters. As a result, we are witnessing an ever-increasing number of compounding disasters and extreme events, which are holding back sustainable development progress.

SDGs and the Sendai Framework, which make clear ensure a sustainable future for all.

SDGs were "disappearing in the rear-view mirror", and urgently need "clear benchmarks on tackling poverty and exclusion, and on advancing gender equality."

Changes are needed to flip systems that are creating risk and instead build resilience as the bedrock

Soon after the adoption of the Sendai Framework for sustainable development. And to guide these for Disaster Risk Reduction and the Sustainable changes, countries and development partners need Development Goals (SDGs) in 2015, there was a to look beyond single SDG indicators to consider the overall impact on people, the planet and prosperity.

> This 2023 special edition of the Global Assessment Report presents a new way of viewing and assessing progress towards sustainable development through the lens of risk and resilience in a changing climate. Resilience, after all, is a key connector between sustainable development. Thus, by measuring and addressing current resilience deficits in a holistic manner, countries could, in turn, build resilience and accelerate progress towards the underlying SDGs.

This year marks the midterm reviews of both the Moreover, the metrics presented in the report can serve as tools for foresight, for planning into that risk-informed sustainable development is no the future, in line with the Secretary-General's longer an option, but an imperative, if we want to 'Our Common Agenda' and his call for a periodic Strategic Foresight and Global Risk Report.

The UN Secretary-General warned this year that the Measuring what is valued reflects societal priorities and provides the basis for the policies to follow. This is why it has never been more important that we understand how to measure and achieve resilience.

> We hope this report will advance this approach and spark the changes needed to achieve development that is resilient for all.

Mami Mizutori

Special Representative of the UN Secretary-General for Disaster Risk Reduction Head of the United Nations Office for Disaster Risk Reduction

ACKNOWLEDGEMENTS

Global Assessment Report on Coordinating lead authors: Disaster Risk Reduction (GAR) **Advisory Board**

Chair

Mami Mizutori, Special Representative of the Secretary General for Disaster Risk Reduction

Members

Kelvin Berryman, Government of New Zealand / Aotearoa: Melody Brown Burkins, Dartmouth College; Kirsten Dunlop, Climate-KIC; Wadid Erian, Cairo University; Wadid Erian, Cairo University; Paolo Garonna, Association of Italian Insurers and Libera Università Internazionale degli Studi Sociali 'Guido Carli'; Yana Gevorgyan, Group on Earth Observations (GEO) Secretariat; Haruo Havashi, Kyoto University; Peter Head, Ecological Sequestration Trust; Ronald Jackson, United Nations Development Programme; Molly Jahn, University of Wisconsin-Madison; Patrick Kangwa, Government of the Republic of Zambia; Kamal Kishore, Government of the Republic of India; Allan Lavell, Latin American Social Science Faculty; Shuaib Lwasa, Makerere University; Malini Mehra, GLOBE International; Asha Mohamed, Kenya Red Cross; Aromar Revi, Indian Institute for Human Settlements; Juan Pablo Sarmiento, Florida International University; Youba Sokona, The South Centre and Intergovernmental Panel on Climate Change; Renato Solidum, Government of the Republic of the Philippines: Alex Wittenberg. Marsh McLennan; and Saini Yang, Beijing Normal University

Jenty Kirsch-Wood, United Nations Office for Disaster Risk Reduction (UNDRR); Angelika Planitz, United Nations Development Programme (UNDP), Matthew Brubacher, (UNDRR Consultant)

Contributing authors

Sophie Lee, Hanoch Barlevi, Neven Knezevic, Farai Maxwell Marumbwa, Jen Stephens, Ingrid Sanchez Tapia, Laura Linda Healy, Margaretha Barkhof, Lars Bernd, Tamara Plush, Omar Robles, Stephanny Ulivieri, Ajoke Onojeghuo, Nicholas Reuge, UNICEF; Erica Allis, Yelena Minasyan, John Harding, Maria Macasil, Bob Stefanski, Valentin Aich, WMO; Pedro Conceicao, Samuel Akera, Babatunde Abidoye, Edvard Orlic, Abdo Seif, Abdulkareem Alsabri, UNDP; Riccardo Biancalani, Patrick Jacqueson, Arbab Khan, Carlo Cafiero, Wirya Khim, Sylvie Wabbes Candotti, Sara Viviani, Anne Kepple, Olivier Lavagned Ortigue, Ingrid Teich, FAO; Steven Kapsos, Catherine Saget, Nicholas Maitre, Marie-Claire Sodergren, ILO; Rui Kotani, Geo Secretariat; David Borges, NASA, Sara Minelli, Barron Or, Sasha Alexander, Daniel Tsegai, Franklin Odhiambo, Brian O'Connor, UNCCD; IUCN; Mark Illife, Gregory Scott, UN-GGIM; Pierre Boileau, Pascal Peduzzi, UNEP; Regina Asariotis, UNCTAD; Sara Valero, Ginette Santana, Antra Bhatt, Sneha Kaul, Toshihisa Nakamura, UN WOMEN; Leonardo Souza, UNDESA, Qudsia Huda, Kai Von Harbou, Heather Adair-Rohani, Kerolyn Shairsingh, Erin Downey, WHO, Esteban Leon, Rosa Ochoa, Anna Karaan, Sovzin Al Youssef, Yana Atonenko, Rosa Surinach, UNHABITAT, Kristen Arnold, WFP, Ioannis Boukis, Ifigenia Paramonou, Eirini Krampi, Ministry for Climate Crisis and Civil Protection, Greece; Roger Pulwarty, NOAA, USA; Cintia Bartz, Municipality of Teresina, Brazil; Nesibu Yasin Seid, Disaster Risk Management Commission, Ethiopia; Andrea Toreti, JRC; Thomas Brooks, IUCN

Map development: Catarina Costa, Vitor Silva, John Schneider, GEM Foundation; Fleur de Lotus Ilunga, Mina Lee, Guillaume Le Sourd, United Nations Geospatial Information Section; Keera Morrish, Brendan O'Neill, Rami Alouta, Environmental Systems Research Institute (ESRI)

Financial resources

UNDRR would like to acknowledge its major core donors for their support to this publication: Sweden, Japan, Norway, Switzerland and Finland.

In addition, UNDRR expresses its deep appreciation to Germany and USA, allowing production of this GAR Special Report 2023. The views expressed in this publication are the author's alone and are not necessarily the views of the donors.

UNDRR internal review:

Paola Albrito, Loretta Hieber Girardet, Jeanette Elsworth, Stefanie Dannenmann-Di Palma, Sandra Amlang, Adam Fysh, Nazgul Borkosheva, and members of the UNDRR Risk Accelerator Group.

Design and production

Project coordinator: Rhea Katsanakis, UNDRR

Project support: Emily Scroope, UNDRR

UNDRR communications and outreach: Jeanette Elsworth, Fanny Langella, Rosalind Cook, Frédéric Delpech, and Ken Hawkins.

Copyeditor: Richard Owsley

Design, graphics and layout: Donna Kirstein

References, sources and image editing: Giovana Santillán

EXECUTIVE SUMMARY

Global warming will surpass 1.5°C above pre-industrial levels during the next decade, due to greenhouse gas emissions. The constant rise in temperatures and related impacts combine with other pressures, thus increasing risk and undermining resilience. The increasing interconnectedness of people and human systems increases the risk of compound and cascading crises.

The maps in this report highlight how factors such as the rapid deterioration of biodiversity, the degradation of land and stress on water resources, lower the capacity of human systems to withstand hazards that are occurring more frequently and with greater intensity. Currently, only 50 per cent of countries have operational early-warning systems and even fewer have legislation in place to connect these systems to preparedness and response plans that can ensure prevention and anticipatory action, as well as response. Humanitarian needs are also rising, as disasters and conflict continue to create enormous human suffering.

While progress continues to be made towards increasing access to electricity, water, healthcare and education, progress towards reducing extreme poverty has been challenged by COVID-19 climate change and other factors (World Bank, 2022a). This has led to growing inequities and pressures on the planet, which are reversing other hard-won development gains. This is particularly the case for lower-income countries, who contribute the least to the causes of climate change and where the most vulnerable populations reside. These adverse impacts occur because the

pursuit of human development has not adequately considered the inadvertent effects on ecosystems and livelihoods. Building in resilience-thinking can accelerate the required paradigm shift for the benefit of people, the planet and prosperity, and future generations. However, interventions and investments in resilience must become more targeted, more systems-oriented and more capable of scaling-up. Systems must not only be able to recover from disasters but need to be adaptive and transformative to build a more sustainable, prosperous and equitable future.


Developed to cover the period 2015-2030, the Sustainable Development Goal (SDG) framework has agreed targets and indicators and a data-gathering system that has been accepted and is being applied by United Nations Member States across the globe¹. Figure 1 shows the existing web of Sustainable Development Goals (SDGs) targets and indicators, that covers key interconnected progress across people, planet and prosperity. However, all too often, the progress data is collected independently in silos. When this same data is looked at holistically from the perspective of resilience-building, key resilience deficits that are holding back sustainable development become evident.

The maps in this report highlight a number of these resilience deficits that are holding back achievement of key sustainable development goals. At the same time, the report's action case examples show that this is not inevitable, and how action is possible on every continent to stop the worsening spiral of risk and disasters and to accelerate SDG target achievement.

Addressing resilience gaps will require the unprecedented scaling-up from with both resilience investment and adaptation action both from within the public and private sectors, particularly for the most vulnerable countries. As these investments take time to mobilize and prepare, delay will increase the inevitable costs. Action is needed now. Disaster risk reduction sits at the nexus between development, humanitarian and climate change action, and can

help foster more-sustainable resilient action in each. Readjusting development pathways requires a reexamination of how prosperity is measured, and a greater emphasis on resilience as key element of sustainable development today and in the future.

Figure 1. Resilient development - people, planet and prosperity



Source: UNDRR, 2023

¹ The Sustainable Development Goals Report 2022 shows that "we still lack timely, high-quality and disaggregate data to fully understand where we are and where we are headed. Investment in data and information infrastructure should be a priority of national governments and the international community" (United Nations, 2022a).


1. WHY RESILIENCE **MATTERS:**

This report explores what risk-informed sustainable development looks like in an increasingly complex and risky world. It highlights how risks are interconnected and how pitfalls can be transformed into opportunities to build resilience. It aims to support government policymakers charged with the difficult and innovative work of risk-informing development to face the increasingly complex set of threats resulting from the deepening climate crisis and other hazards. It also aims to highlight how resilience-building must be central to the framing of a more risk-informed post-2030 agenda.

The Sustainable Development Goals (SDGs) provide The impacts of climate change are causing existing a framework of agreed collective goals for attaining hazard events to become more intense and occur with sustainable development entitled Transforming Our (United Nations, 2015a). United Nations Member creating compound crises, a phenomenon increasingly States are mandated to collect and report data on their referred to as a polycrisis. Left unaddressed, these progress towards achieving their SDG targets. Using this compound crises draw increasing amounts of resources information to assess resilience deficits at the macro into reactive responses rather than into prevention for scale is a 'quick win' to identify where risk reduction is building long-term resilience. These reactive responses needed. Given the imperative to transition to a carbonneutral development model, understanding where resilience-building can create positive feedback loops amplify vulnerabilities and distract from addressing the and co-benefits is particularly important now.

greater frequency. These impacts combine with other World: The 2030 Agenda for Sustainable Development risks and threats such as conflict, epidemics or inflation, can lead policymakers to choose maladaptive policies, which inadvertently worsen the impacts. Such trends root causes behind these risks.

Figure 2. Core elements and aims of resilient sustainable development



Source: Nadin, R. and Opitz-Stapleton, S. (2019) Figure 2: Risk-informed development and its core aims. In: Risk-informed development: from crisis to resilience. ODI and UNDP.

To reverse this downward spiral, countries and communities need to build systems that can prevent or better manage risk. This can include taking action such as investing in resilient infrastructure that can withstand disaster impacts, improving early-warning systems to reduce losses, and improving economic and social opportunities that can reduce underlying vulnerability to hazards. This ability to withstand risk, and recover from Framework for Disaster Risk Reduction 2015-2030

disasters, in a manner that is transformative and bounces forward, is at the root of resilience (Alessi et al., 2020).

Urgent action to reduce risk is fundamental to simultaneously achieving the SDGs of the 2030 Agenda (United Nations, 2015c), the targets of the Paris Agreement (United Nations, 2015a) and the Sendai

Table 1. Definitions of resilience

Definitions of resilience

PEOPLE

"The ability of a system, community or society exposed to hazards to resist, absorb, accommodate, adapt to, transform and recover from the effects of a hazard in a timely and efficient manner." (UNDRR, 2017)

"The ability of individuals, households, communities, cities, institutions, systems and societies to prevent, resist, absorb, adapt, respond and recover positively, efficiently and effectively when faced with a wide range of risks, while maintaining an acceptable level of functioning and without compromising long-term prospects for sustainable development, peace and security, human rights and well-being for all." (UN CEBC,2020)

PLANET

"The capacity of social, economic, and environmental systems to cope with a hazardous event or trend or disturbance, responding or reorganizing in ways that maintain their essential function, identity, and structure, while also maintaining the capacity for adaptation, learning, and transformation." (IPCC, 2018)

PROSPERITY

"Economic resilience has two components: instantaneous resilience, which is the ability to limit the magnitude of immediate production losses for a given amount of asset losses, and dynamic resilience, which is the ability to reconstruct and recover." (World Bank, 2014)


(United Nations, 2015b). The pathways to achievement Building resilience makes physical assets stronger, are inextricably linked, and positive action towards one needs to accelerate achievement of the others. It does of working. As a concept, resilience can describe a not have to be a trade-off.

Fostering resilience requires governments, the private sector and civil society to better understand how choices or inaction to promote societal well-being (people), ecological or biosphere well-being (planet) and economic well-being (prosperity) interact to build or undermine resilience. The increasing interdependence of ecosystems and humanity reinforces the need to maintain the resilience of all systems. This is why the people, planet Creating the conditions for sustainable development and prosperity paradigm is integral to forging sustainable development pathways, and why actions to promote peace and partnerships are so essential.

Understanding how to identify and measure vulnerabilities, or deficits, in resilience, as well as how to develop interventions that address current and future needs, is at the core of sustainable development. Figure 2 shows how becoming risk-informed is integrally linked to action that mitigates risk by avoiding poor development choices, reducing vulnerabilities and promoting the continual review and learning of resilience-building.

and also creates more sustainable systems and ways system trait (e.g. a disaster-resilient water-supply system), a process (e.g. resilient agricultural practices) or an outcome (e.g. a resilient city) (Moore et al., 2017). Strengthening resilience is critical to withstanding and responding to shocks and to achieving a country's development objectives (United Nations, 2020). Table 1 shows the definitions of resilience related to people, planet and prosperity.

requires accelerated transformations in key systems, including food, water and energy, making them more effective at addressing growing demand while sustainably managing natural resources.



GAR23: Special Re


2. UNDERSTANDING RISK TO PEOPLE, THE PLANET AND **PROSPERITY**

Risk is a function of how a hazard combines with vulnerability and exposure (Figure 3) (UNDRR, n.d.a). In other words, understanding the risk posed by hazards requires a better understanding of vulnerability and exposure. Vulnerability refers to the conditions determined by physical, social, economic and environmental factors or processes that increase the susceptibility of an individual, a community, assets or systems, to the impacts of hazards. Exposure refers to the location of people, infrastructure, housing, production capacities and other tangible human assets in hazard-prone areas. Disasters occur when any of these elements of risk is not reduced or adequately managed.

future relationships among hazards, vulnerability and country, and how they are likely to change in the future, exposure. For example, the most pressing way to reduce is necessary to pre-emptively adapt to those impacts. climate hazards currently is to reduce greenhouse gas emissions, which are currently making climate- The ten resilience deficits, illustrated by 15 maps related hazard events more intense and more frequent. below, show how hazards are increasing vulnerability

The choices and action taken today will affect the Understanding how those hazards lead to disasters in a

Figure 3. Options for risk reduction through adaptation



Source: Adapted from (IPCC, 2019a)

and creating deficits in SDG progress. Combing risk modelling and drawing on the IPCC Representative Concentration Pathways (RCPs), assuming that the world will pass 1.5°C of warming above pre-industrial levels by the 2030s, the maps highlight the impacts of hazards, such as heatwaves, drought and air pollution, to show how they progressively inhibit progress in attaining the development objectives. In so doing, the maps utilize the SDGs to show the resilience gap found in people, planet and prosperity. Drawing from IPCC, the maps have been developed through a process of cocreation, drawing on expertise from across the United

Nations system. Experts from technical United Nations agencies such as UN DESA, UN-Habitat, UNDP, WHO, UNCTAD, UNCCD, FAO, UNICEF, ILO and the UN Map Division, worked with UNDRR and a team of expert global modellers to interrogate existing SDG data, available hazard maps and foresight data for climate change and other key drivers, such as demographic and urbanization trends. The maps are not presented as static projections, but instead show key inter-relationships across people, planet and prosperity SDG indices, and point to future potential development pathways based on business and usual action. A more detailed explanation of the sources

and methodology is available in the last chapter of this Taken together, the maps demonstrate why sustainability report and on the UNDRR website². An online version of maps and openly available data is available through the Exchange (UNDRR, n.d.b).


Pathways (RCPs), which describe four different 21st century pathways of greenhouse gas (GHG) emissions all three. and atmospheric concentrations, air pollutant emissions and land use (IPCC, 2014)." RCPs range from RCP 2.6 (low-emission scenario) to RCP 8.5, which is the highest emission scenario. At the time the Representative Concentration Pathways (RCPs) were published, they developments in the absence of climate policy: RCP4.5, RCP6 and RCP8.5, described as, respectively, low, medium and high-end scenarios in the absence of strong climate policy (van Vuuren et al., 2011). RCP8.5 was described as representative of the top 5 per cent scenarios in the literature." (IPCC)

In this report, estimates of urban damage due to floods are based on RCP 4.5, and work hours lost due to heat stress estimates are for RCP 2.6 and 6.0. Global-warming levels, which represent the increase in global surface air temperature from the pre-industrial era are applied to maps that depict drought projections, mean near surface air temperature and extreme sea levels.

As many of the SDG indicators are interrelated, the maps attempt to show some of these connections and to highlight the need to develop, longer term, moreintegrated systems and analysis. They show that although progress is being made in attaining several SDG objectives, the way this progress is attained is itself often causing the pressures on planetary systems. These pressures, including increasing impacts of climate change and resource scarcity, are undermining progress in other SDGs. For example, while more people have access to electricity, the generation of that electricity is predominantly from the burning of fossil fuels, which contributes to climate change.

requires maintaining a balance between key systems, including the social (people), ecological (planet) cited agencies and through the UNDRR Risk Information and equitable economics (prosperity), to achieve resilient sustainable development. Recognizing the interdependence of these systems will reduce one This report refers to "The Representative Concentration" progressing at the expense of the other, and it will create opportunities for synergies to improve the well-being of

The case examples that accompany each map show that action to reduce resilience and thereby accelerate sustainable development is possible, but needs to be scaled-up urgently. Key elements for how to do this included three scenarios that could represent emission are the subject of Chapter 3 and draw on existing good practice lessons from the sustainable development, climate change and DRR communities. Finally, Chapter 4 encourages a re-examination of the way prosperity and development are defined and conceptualized, and draws a series of conclusions as to how competing interests can be rebalanced to attain more-sustainable development pathways.




² www.undrr.org

Resilience deficit 1. Access to disaster early-warning systems

Map 1. Average number of people directly affected by disasters between 2005 and 2021, and countries with a currently operational multi-hazard early-warning system in 2022 (SDG indicators 1.5.1, 11.5.1 and 13.1.1)

The number of recorded disasters has increased fivefold over the past 50 years, driven in part by human-induced climate change (WMO, 2023). This trend is accelerating. Map 1 shows the prevalence of people affected by disasters and the countries that currently have operational early-warning systems (EWS). 62 million people directly affected by disaster in the last two decades live in countries without operational EWS. This means that without increased investment in resilience-building through extending early-warning-system coverage, developing countries are projected to have higher numbers of people affected by hazards as population growth continues. Map 2 shows this data in the context of future population growth, highlighting how exposure is increasing in countries where there is already a large number of people affected by disasters.



Source : Sendai Framework Monitor UNDRR, 2022

The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.2



Map 2: Average number of people directly affected by disasters between 2005 and 2021, and projected relative change in total population between 2022 and 2050 (SDG indicators 1.5.1, 11.5.1 and 13.1.1)

Provided risk reduction measures are taken, increased exposure addressed. Against this backdrop, and despite the increasing does not necessarily need to result in increasing casualties and unmber of people being affected by hazards, the number of economic costs. Fortunately, as indicated in Map 1, most of the mortalities due to hazards over the past 50 years has decreased countries with the greatest exposure to hazards already have early-warning systems. These systems are already proving themselves effective in reducing the impact of hazards. And even where early-warning systems are in place, many have gaps (World Meteorological Organization, 2018) that need to be urgently

threefold (WMO, 2021).

The proven capacity of these systems underlies the launch by the United Nations Secretary-General of the Early Warnings for All (EW4All) Initiative in 2022. This initiative aims to ensure the

whole world is covered by an EWS by the end of 2027. To save lives and livelihoods, EWSs need to be multi-hazard and connected to early action. They can be particularly effective if they are combined with investment in climate-resilient infrastructure such as floodcontrol systems, strengthening building codes and protecting environmental buffers, and are developed with the involvement of communities at risk (Rogers and Tsirkunov, 2011).

Key figures



126 countries with disaster risk reduction strategies (UNDRR, 2022b). (SDG indicator 1.5.3) (UN DESA, 2021)




97 (estimated) Countries with early-warning systems (UNDRR,



4.2 trillion Net benefit of investing in resilient infrastructure in developing countries over the lifetime of the new infrastructure. There is a \$4 benefit for every \$1 of investment (Hallegatte et al., 2019).



66% Number of local governments that adopted disaster risk reduction strategies in 2021 (The Statistics Division of the United Nations Department of Economic and Social Affairs, 2022).



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatia



ACTION CASE: BARBADOS


Fully exploiting the potential of early-warning systems

EWSs are becoming increasingly vital tools for the threat of vector-borne diseases is mounting.4 reducing hazard vulnerability. Their ability to forecast After a particularly costly outbreak of dengue fever hazards and communicate risk assessments to those in 2017, Barbados took steps to add biological risk affected is made possible by integrating multiple forecasting to its EWS (Zeng et al., 2021). To do so, the science, technology and human systems. This Barbados Ministry of Health and Wellness partnered interconnectivity is important to assess the scale with national and regional climate organizations to of ecological impacts and create the institutional develop climate-informed disease-forecast models. collaboration needed to pre-emptively reduce The system created through this transdisciplinary vulnerability to the threats.

to great effect is Barbados.³ As a Caribbean island, climate-health bulletins inform a variety of networks, Barbados is regularly exposed to numerous hazards, which are then able to take pre-emptive action to including floods and hurricanes. In 2022 alone, reduce outbreaks of vector-borne diseases.5 the island experienced multiple storms and eight hurricanes that caused widespread damage. The In February 2023, in recognition of the country's country's EWS, which combines data sources ranging innovation, Barbados hosted the launch of the from the Pacific Tsunami Warning Center to Google United Nations EW4All initiative. As part of the of Play, is at work every day to reduce the impact of all Climate Risk and Early Warning Systems Caribbean types of meteorological hazards.

As climate change creates greater weather variability, However, as higher temperatures combine with floods, collaboration had the capacity to predict disease outbreaks weeks, if not months, in advance (Lowe et One country that expanded the design of its EWS al., 2020). Disease forecast reports, risk maps and

> initiative, Barbados continues to demonstrate the cost-effectiveness of EWS as a critical disaster risk reduction and climate change adaptation measure that reduces economic losses and saves lives.6 The ability of Barbados to integrate disease-forecasting into its EWS shows the expansive capacity and versatility of these systems.



The main vector-borne diseases are dengue, chikungunya and zika.




One particular challenge is to treat standing water to reduce mosquito proliferation in a manner that also ensures water security, as water

⁶ The other example of a biological risks being integrated into EWS is in Europe. The Early Warning Systems for Vector-Borne Diseases is part of the European Centre for Disease Prevention and Control, increasing the lead time needed for a public-health response to disease emergencies (Climate-ADAPT, 2022).

Resilience deficit 2. Increasing drought risk and food insecurity

Map 3. Percentage of country area exposed to increased drought frequency under a 1.5°C climate-change scenario and current prevalence of moderate or severe food insecurity in the total population (SDG Indicator 2.1.2 and 2.4.1)



Source . GAN Special Report on Droughly 2021

The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.3 Jun 2023



Map 4. Percentage of country area exposed to increased drought frequency under a 2.0°C climate-change scenario and average prevalence of moderate or severe food insecurity in the total population between 2019 and 2021 (SDG Indicator 2.1.2 and 2.4.1)

Key figures



70% Percentage employment

in low-income countries reliant on agriculture as source of income (World Bank Group, 2017)



60% Increase in incidents of drought by the end of the century (IPCC, 2014)



71 Additional food, feed and fertiliser trade restrictions imposed by countries in 2022 (World Trade Organization, 2023)



80% Percentage of global population at risk of crop failure and hunger in sub-Saharan Africa and south and south-east Asia. (The World Bank. 2022)


Globally, drought is one of the most lethal hazards (WMO, 2021), mainly because it increases food insecurity, which brings with it a cascade of highly damaging impacts. Due in part to climate change, incidents of drought have doubled in the last 40 years and their geographic range has expanded. This is reversing gains in food security and poverty reduction (FAO, n.d.a). Between 2014 and 2020, the prevalence of moderate to severe food insecurity rose by 22 per cent to 30 per cent with the highest rises in sub-Saharan Africa, central and south Asia and Latin America (FAO, n.d.c). Map 3 illustrates how drought, along with conflict and the COVID-19 pandemic, has contributed to a record increase in people facing acute food insecurity. In 2022, a new record was reached, with 345 million people facing acute food insecurity globally (WFP, n.d.).

Maps 3 and 4 show the percentage of a country's total area that will be exposed to increased drought frequency under the 1.5°C and 2.0°C climate scenarios respectively. Under the 2.0°C scenario, 103 countries will have increased drought

Acting now to build resilience towards drought and foodsecurity risk can stop this negative spiral and would accelerate

achievement of multiple SDGs including 1, 2, 3 and 10.

frequency in at least 85 per cent of their territory.



Source : GAR Special Report on Drought, 2021

The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.4 Jun 2023



ACTION CASE: SAHEL REGION

Accelerating the greening of the Sahara through the Great Green Wall initiative

Managing slowly but steadily increasing pressures, such as desertification and soil erosion, requires durable and long-term responses. Setting these responses in motion early is important given the long lead times needed to steadily offset these encroaching risks. One example of such a durable response is the creation of a Great Green Wall (GGW) of vegetation along the southern edge of the Sahara, to counter climate impacts.

The idea gained traction in 2007 after its endorsement by the African Union. The aim is to restore 1 million km² of degraded land across 7,000 km of the Sahel, with the support of the 11 affected States and regional bodies. Although the original purpose was to counter desertification, the initiative broadened to focus on improving the livelihoods of the people who are largely dependent on rain-fed agriculture and livestock (FAO, 2014).

temperatures expected to rise by 3-6°C by the end of this century (Niang et al., 2014). Rainfall patterns are also becoming unpredictable and more intense, thus making agriculture production challenging (Sultan and Gaetani, 2016). The planting of GGW vegetation provides numerous benefits as it sequesters carbon and improves water retention, thus lowering the risk of floods and improving soil productivity. The vegetation also provides shade and food for animals.

One of the less-recognized contributions of the GGW, is that it works with another process triggered by climate change - the greening of the Sahel. Precipitation rates and vegetation have been increasing since the droughts of the 1970s (Brahic, 2005). This greening of the Sahel, at least in its western regions, is due to changing monsoon patterns. Rather than moving humidity to the Atlantic, it is now starting to come back (Pausata et al., 2020). The water retention and transpiration of plants, including those being planted as part of the GGW, accentuate this greening process.7

Although most of the region may become wetter, increasing temperatures and evaporation will offset some of the benefits of higher precipitation.8 Therefore, more-resilient vegetation, agriculture and methods of managing livestock and human health will be needed to adapt to the changing climate. While the GGW mitigates droughts and floods and provides a range of economic The Sahel is a hotspot for climate impacts, with and social benefits, managing slow-onset variables requires constant review and adaptation.



The Sahel is a hotspot for climate impacts, with temperatures expected to rise by 3-6°C by the end of this century



more-resilient vegetation, agriculture and methods of managing livestock and human health will be needed to adapt to the changing climate.

The planting of GGW vegetation provides numerous benefits

as it sequesters carbon and improves water retention, thus lowering the risk of floods and improving soil productivity. The vegetation also provides shade and food for animals.



A 'Great Green Wall' in the region could result in more rainy days (+9 per cent) and intensified heavy-rain events while reducing extreme dry spells. (Saley et al., 2019); (Zachos et al., 2008); (Goffner et al., 2019); (Yosef et al., 2018).

Less Saharan dust could reduce ocean and Amazonian productivity, for example, thus making afforestation potentially less effective as a arbon sink. (Ridgwell et al., 2022)

Resilience deficit 3. Forced displacement and negative education outcomes

Map 5. Estimated number of internally displaced children (under 18) at the end of 2022 and youth-literacy rates (latest estimate since 2014) (SDG indicator 4.6.1)

Ensuring all children obtain a quality education is fundamental to creating a peaceful and prosperous world (United Nations, n.d.a). Forced displacement caused by conflict, epidemics and suddenonset hazard events, is highly disruptive to children's education. According to the Internally Displace Monitoring Centre, of the 71 million people displaced at the end of 2022, 30 million were under the age of 18. (Internal Displacement Monitoring Centre, 2023). According to the United Nations Refugee Agency, among those children classified as refugees, 61 per cent go to primary school, compared to 91 per cent globally (UNHCR, n.d.). This number does not include the many millions of people who are displaced within their countries who do not qualify as refugees.

Displaced children often fall behind with their education, and their pathway to higher education and career opportunities narrows. For example, data on children displaced by conflict show that only 23 per cent enrol in secondary school, with that number dropping to 9 per cent in low-income countries (UNHCR, n.d.). By the time they reach university age, only 1 per cent move on to higher education (UNESCO, 2019). This limits the future of these children and results in the loss of tens of trillions of dollars in lost lifetime productivity and earnings (World Bank, 2018).

Map 5 shows the challenge of ensuring that children and youth are able to gain literacy skills in societies already experiencing high rates of internal displacement. Given that climate change is increasing internal-displacement risk in many ways, including making some coastal areas uninhabitable, changing crop suitability and even in some cases increasing conflict risks, increased investment to build resilience and prevent displacement where possible is essential.

However, in some cases, human mobility is also a key accelerator of sustainable development and can be a positive form of risk reduction when undertaken in a consultative, safe and voluntary manner, as showcased in the example of Fiji below.

Key figures



330 million Children exposed to climate and environmental hazards in 2020 (UNICEF, 2021)




820 million Number of **children exposed to heatwaves** in 2020 (UNICEF, 2021)



920 million Number of **children exposed to water scarcity** in 2020 (UNICEF, 2021)



2 billion Number of people affected by armed conflict in 2023 (United Nations, 2023b)



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatia Map No. 4673.5



ACTION CASE: FIJI

Pre-emptive voluntary relocation of communities to reduce exposure to disasters

Being able to forecast climate impacts and develop collective understanding of the realities of risk and limits to adaptation is critical to creating moreadaptive and anticipatory governance. This capacity enhances adaptive capacities and manages what can be painful but necessary trade-offs. This is the case for many communities in Fiji, who are at the forefront of the climate crisis as they are losing land, livelihoods, traditional fishing grounds and cultural assets due to seal-level rise, coastal erosion and recurring disasters. The development of a collective understanding and realization of these climate risks has led them to make a decision about whether to stay in their homes or relocate to safer locations where they would be more secure (Lyons, 2022). The process of deciding which communities to move first, where to move them, and how, also requires a deep understanding of inter and

intra-communal relations, land-tenure rights and a host of other considerations.

Fiji comprises over 300 islands, with a population of just under 1 million people. Much of the population is exposed to climate-induced impacts since many of its communities are located near the coast (World Bank Group, 2021). The country is no stranger to cyclones, which can hit several times a year. However, as the ocean warms, these storms are intensifying, and storm surges are moving deeper inland due to sea-level rise.

To address the growing concerns of its population and avoid further loss of life and property, the Fiji Government embarked on the first pre-emptive population-relocation programme due to climate impacts.

The government conducted an in-depth assessment of current and prospective climate impacts. It also established local community-consultative processes so community members could express their concerns and participate in the decision-making processes. One remarkable feature of the programme is that to ensure consensus, a decision to move requires 90 per cent agreement among all sectors of a community including women, youth and people with disabilities. If a community does not want to relocate, people are not forced to do so. Similarly, the responses of any receiving community are also considered. Through this process, 42 villages were identified for relocation. Of these, six have already moved. The process of relocating entire villages is challenging. Land claims need to be resolved, infrastructure with the requisite services needs to be built, and processes need to be made to support the often-traumatic process of leaving ancestral land.

To facilitate the movement of a community, relocation of schools and lowering disruption to children's education is always among the top priorities. To learn from each experience, with the support of the UNDRR, the Government developed a comprehensive risk and vulnerability methodology to inform standard operating procedures for planned relocations (UNDRR, 2019). These procedures are continually adapted as the

programme is implemented. In this way, lessons are learnt, thus improving the way in which future relocations are conducted. The learning process allows the Government and local authorities to continually review the risks and mitigation processes, thus minimizing risk and avoiding inadvertent damage.

Developing a shared understanding of climate risks, such as those affecting Fiji, is vital to developing consensus on how to manage those risks. Pre-emptive relocation is unfortunately one that is likely to be repeated elsewhere. The way the Fijian Government and communities took time to fully appreciate the situation, including avoiding disruptions to education, offers valuable lessons for other communities exposed to climate impacts.



the Fijian Government has embarked on the first pre-emptive population relocation programme due to climate impacts.





Resilience deficit 4. Increasing water stress and population growth

Map 6. Level of water stress in 2020 and projected relative change in total population between 2022 and 2050 (SDG indicator 6.4.2)

Map 6 shows how population and economic growth, combined with the impacts of climate change, are rapidly increasing demand on water resources. That means that by 2050, the total population in countries with critical water stress is expected to increase by 50 per cent, from 620 million currently to 933 million in 2050. Sustainably managing water resources requires that the amount of fresh water utilized is recharged by rainfall and the recycling of water. If this does not occur, the stress on water systems will steadily diminish groundwater storage.

More than two billion people are living in countries under water stress and 3.6 billion people face inadequate access to water at least one month a year. By the end of this decade, due to population and economic growth, demand for fresh water is expected to outstrip the supply by 40 per cent. As shown in Map 6, the level of water stress is likely to increase in the Middle East and West Africa due in part to population growth and increasing consumption.

Drought is both a symptom and a cause of water stress. While drought occurs when there are abnormally long periods of low rainfall, the impact on livelihoods, agriculture and livestock occurs when there is no longer enough water to meet demand. Drought amplifies water stress while the lack of water aggravates droughts (World Health Organization, n.d.b). Climate change is exacerbating this problem, as higher temperatures and lower humidity cause droughts to increase in frequency and severity. Africa is particularly vulnerable and has already suffered a 29 per cent increase in the number of droughts over the past two decades (World Health Organization, n.d.b).

Given the number of competing priorities, the solutions are complex and require multiple systems to work together. One of the best ways to encourage this collaboration is through integrated water-resources management (IWRM). This aims to forge integrated water planning that optimizes management of the supply and use of water. Countries with the capacity to implement IWRM processes tend to be more sustainable, with lower levels of water stress.

Key figures



12% Global improvement in water-use efficiency between 2015 and 2019 (FAO, 2022b) (SDG indicator 6.2.4)

74% Global population that uses safe

drinking-water services in 2020 (UN-


Water, n.d.)



54% Countries that developed integrated water strategies in 2020 (UNEP, 2021)



19% Amount of global water resources used sustainably in 2020 (FAO and UN-Water, 2021)



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.6 Jun 2023



ACTION CASE: YEMEN

Transformation within crises

The availability and affordability of water underpins the economy, livelihoods and health of any society. in precipitation, and greater demand, requires an infinite resource.

Yemen has always had to deal with water scarcity. Its communities have developed multiple coping mechanisms to adapt to arid conditions, using agricultural techniques such as terracing to capture water flows. However, the advent of electricity has groundwater extraction. Lured by cash crops such as constituting 93 per cent of water consumption (UNDP, the United Nations Development Programme and 2022a).


Together with a rapidly increasing population, water solutions. Understanding the implication of trends tables in the country are falling several metres every and working with the incentives that they create year. As a result, by as early as 2025, the period of can reveal opportunities for making long-overdue 'easy water' is likely to be over, as non-renewable structural changes. water reserves empty.

The coming end of easy water in Yemen is as foreseeable as it is certain. However, the lack of political will, coupled with fragmentation due to conflict, has impeded collective efforts to build a more sustainable system. To avoid feedbacks between water scarcity lowering agricultural outcome which feeds intercommunal tension, a host of interventions are needed (UNDP, 2022a).

With the right preparations and sufficiently early investments, the worst-case results can be averted, and a more resilient and integrated system of using

No other resource is more consequential than water. renewable water created. Efforts that are already creating ecological and economic dividends include working with farmers to restore traditional farming Sustainable management of water, in a context of practices including terracing, rainwater harvesting increasing temperature and greater intermittency and the promotion of drought plant species. This includes working with khat farmers to change the depth understanding of the limits to managing this incentives so that this water-intensive crop can be replaced with one that is both nutritious and has value as an export. It also includes building moreinclusive governance modalities such as local water-user associations, which encourage collective decision-making on the allocation and management of water resources.

significantly increased pressure on water resources Yemen has many challenges, and understanding the as agriculturalists were able to significantly increase drivers of these challenges and their consequences is vital to developing the appropriate response khat, demand for water has soared, with agriculture (IPCC, n.d.a). Partnerships with organizations, like civil society organizations, are helping communities to understand their risks and to find sustainable



Resilience deficit 5. Increased land degradation and biodiversity loss

Map 7. Percentage of degraded land in 2019, and the IUCN Red List of Threatened Species Index for 2020 (SDG indicators 15.3.1 and 15.5.1)

Protecting biodiversity is essential for maintaining the integrity of the ecosystems on which humanity depends. Land degradation, most of which is due to converting land for agriculture, is the primary driver for biodiversity loss (IPCC, 2019b). Agriculture alone is the primary threat to 24,000 of the 28,000 (86 per cent) species at risk of extinction (Benton et al., 2021). One in four species are threatened with extinction.⁹ The world is losing approximately 100 million ha or 1 million km2 of land to degradation every year (UN DESA, 2023b). So, while food productivity has increased, the practices utilized undermine long-term food security and ecosystem functioning.

As shown in Map 7, land degradation, much of which is due to deforestation and unsustainable agriculture practices, contributes to biodiversity loss. The Red List Index measures the total change in the extinction rate of all species. Land degradation also contributes to indirect losses due to the release of carbon from the soil, which decreases its productivity and ability to absorb water.

Reversing this trend requires policies that encourage sustainable land-use management, including allowing nature to restore the land. This is the commitment made at the United Nations Convention on Biological Diversity in 2021 when countries committed to protecting 30 per cent of land and 30 per cent of ocean by 2030. Realizing this is fundamental to maintaining the stability of the ecosystems on which human prosperity is based.

Key figures



1% Increase in global proportion of forest area within protected areas, between 2010 and 2020 (FAO, n.d.d)



7% Increase in forest area under management between 2010 and 2020 (FAO, n.d.d)



5-20% Amount of carbon emissions that can be offset through the better management of soils (IPCC, 2019b)




90% Loss of forest due to agriculture between 2000 and 2018 (FAO, n.d.b)



-9.2% Red List Index overall extinction of species between 2000 and 2022 (SDG indicator 15.5.1) (UN DESA, 2022)



37% Number of countries on track to meet their national biodiversity targets (UN DESA, 2022)



⁹ The primary drivers of biodiversity loss are changes in land and sea use, direct exploitation of organisms, climate change, pollution and invasion of alien species (IPBES, 2019).

UNITED NATIONS Geospatial Map No. 4673.7 Jun 2023



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

ACTION CASE: INDONESIA

Creating a steady state in the governance of natural resources in Cidanau Watershed

Reaching a steady state where consumption remains at or below the carrying capacity of natural ecosystems, on which Indonesia's rich biodiversity relies, is critical to sustainability. On Java Island in Indonesia, finding this steady state between the water produced by its watershed and the increasing demand of its cities and industry was challenging. A solution became possible only after different actors, each with their own set of interests and decision-making, came together to achieve a common and mutually beneficial objective that was good for both the economy and the environment.

The Cidanau Watershed is a nature reserve created to preserve the rich habitat of Indonesia's native species. It is also the primary source of fresh water for two districts in Java: Serang and Pandeglang. It provides water for the citizens of the main city, Cilegon, as well as to over 100 industries, including the largest steel maker in south-east Asia, the Krakatau Steel Company. The water generated for the city comes from the only mountainous area on the island. The capacity of this ecosystem to provide fresh water came under threat due to deforestation for agricultural purposes. The resulting erosion reduced and polluted the water, clogging waterways. As the mountains are protected as a nature reserve, the

government initially tried to resettle farmers and reforest the area, but these efforts had little success due to lack of agreement with the farmers.

To address the situation, the local government and a civil society organization, Forum Komunikasi DAS Cidanau (FKDC), brought the private sector and farmers together to find a solution. Instead of one actor deciding a course of action, all stakeholders decided on creating a Payment for Environmental Services (PES) scheme. In a PES, those that benefit from ecoservices pay those conserving the nature (Ostrom, 2010). that provides them (Amaruzaman et al., 2022).

In this case, the Cidanau-based industries provide payments to farmers who maintain forests through agroforestry practices. The local government is an investor in this scheme and FKDC certifies that both sides fulfil their part of the deal. Started in 1994, the Cidanau Watershed PES is one of the longest-running schemes in the world and has the full support of the national and local governments. This example demonstrates how polycentric governance works when there is political will from all actors, a common legal framework and higher-level governance support (Ostrom, 2010).



Resilience deficit 6. Increased heat stress and energy consumption

Map 8. Energy efficiency in 2020, share of modern renewables in total energy consumption in 2020 and mean near-surface air temperature under a 2°C warming scenario SSP2-4.5 (SDG indicators 7.2.1 and 7.3.1)

The pace of the energy transition is currently well below what is required to achieve carbon neutrality by 2050. As shown in Graphic 1 on modern renewable energy, the percentage of renewable energy has doubled between 1990 and 2020 from 6 per cent to 12 per cent. However, as more people are using more electricity, the overall consumption of fossil fuels also continues to rise (Economist Intelligence Unit, 2022). To get ahead of increasing energy demand, investments need to be significantly increased, to create more clean energy and to use that energy more efficiently.

Key figures



\$5.9 trillion Global expenditure on fossilfuel energy subsidies in 2020, (SDG indicator 12.c.1) (International Monetary Fund, 2022)




91% Population with access to electricity in 2020; up from 83% in 2010 (SDG indicator 7.1.1) (UN DESA, 2022)

2% Increase in modern renewable-energy use in final energy consumption (2010-2019) (SDG indicator 7.2.1) (UN DESA, 2022)



-3.2% Amount of yearly energy-efficiency improvement needed to reach target by 2030 (SDG indicator 7.3.1) (UN DESA, 2022)


Graphic 1 Share of modern renewables in the total energy consumption 1900-2019 (%)



Source: UN DESA, 2023 prepared for this report

Heat negatively affects electricity production while simultaneously increasing demand due to the need for cooling. As shown in Map 8, many of the countries with the lowest rates of energy efficiency and renewable energy are also the most affected by heat stress due to climate change.

Global efforts to reach carbon-reduction objectives through electrification are driving a race to decarbonize the electricity sector. This race can be won only by improving energy efficiency and switching to less carbon-intensive forms of production, namely renewable energy. However, installation of new renewable capacity needs to outpace demand.



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.8



ACTION CASE: INDIA

Combating heat using a participatory approach

When addressing threats as widespread and deadly as heatwaves, any risk-mitigation plan requires extensive participation of the affected population. India has therefore implemented heat action plans (HAPs) in cities across the country through the broad participation of the public and local governments.

Often referred to as the 'silent killer of climate change', increasing heatwaves are among the most impactful of hazards, particularly in tropical and subtropical climates such as India. Exposure to this risk is high in India because of its geography, strong population growth and urbanization. This exposes more people to the risk, and urban areas, particularly slums, tend to act as heat islands due to paved surfaces re-radiating heat.

Cities trap heat and often also have higher concentrations of air pollution. Cities produce roughly 78 per cent of carbon emissions, the majority of which come from the energy sector, and substantial airborne pollutants that adversely affect the populations living within them. When combined with heat stress, the adverse impacts of pollution on human health increase. Heat tends to oxidize pollutants, thus increasing stress on a body that is already weakened by the need to regulate temperature. The net result of the combination of high pollution and heat is that the risk to mortality increases by as much as threefold.

To reduce exposure, save lives and reduce overreliance on air conditioning, the Indian Government, municipalities and local organizations are increasingly implementing HAPs. As there is no one-sizefits-all approach, each plan is developed locally through broad participation and consultation. This consultative process is always the first step as it builds engagement and confidence in the system, and allows a greater array of resources to be utilized. Broadening support ensures there is political support from local governments, weather data from meteorological agencies, and input from civil society and universities.

While each HAP is tailored to the local context, they all have essentially four characteristics:

- A graded EWS, from mild to severe
- A public-awareness campaign on dangers and mitigating measures
- Trained medical staff and facilities that are prepared

Systems and infrastructure to improve water distribution and roof-cooling programmes, to shade spaces and to expand public gardens.

Since the first HAP was implemented in Ahmedabad in 2013 to broad success, the programme has expanded to 23 of India's most heat-prone states, with each following the Government's National Disaster Management Authority Heat Guidelines (NRDC, 2022). The Government and review studies credit HAPs as having saved thousands of lives, due to their participatory and flexible approach.



increasing heatwaves are among the most impactful of hazards, particularly in tropical and subtropical climates such as India.



Resilience deficit 7. Increased air pollution and mortality

Map 9. Ambient air pollution measured by the annual mean levels of fine-particulate matter and ambient air-pollution-attributable death rate (SDG indicator 11.6.2)

Air pollution kills approximately 6.78 million people a year (World 20 countries with the highest population increase, which means Health Organization, 2022) (United Nations, 2019). Of these, 3.5 million deaths are attributed to outdoor pollution while 3.8 million deaths occur due to indoor air pollution. Indoor air pollution is caused by cooking with wood, coal and kerosene, and disproportionately affects women and girls (World Health Organization, 2022). Map 9 shows the correlation between the lack of access to clean fuels and air pollution that leads to higher mortality rates. This map also shows the disparity between developed economies where clean fuels predominate and developing countries where traditional means of cooking remain common. Eight of the 20 countries with highest mortality rate due to air pollution are also among the

that mortality is likely to further increase without urgent action to address this resilience deficit. Action is possible, and often has other positive benefits. Switching to the use of cleaner fuels like solar, wind or biogas reduces pollution. Policy choices to apply subsidies, facilitate microfinance and deploy tax incentives can facilitate a fair and rapid transition to a cleaner, more-resilient energy mix (World Health Organization, n.d.a).

Key figures



2.4 billion

People without means of clean cooking (SDG indicator 7.1.2) (UN DESA, 2022)



11% Reduction in global fineparticulate matter pollution

between 2000 and 2019 (SDG 11.6.2) (World Health Organization, 2023a)




5% Percentage of total global energy use consumed to cool in buildings globally in 2017 (International Energy Agency, 2018)



99% Urban population that lives in areas exceeding World Health Organization guidelines on air quality (UN DESA, 2022) by 2030 (SDG indicator 7.3.1) (UN DESA, 2022)



69% `Percentage of people using clean fuels for indoor cooking (up from 50% in 2000) (WHO, 2023)




The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations. Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatia Map No. 4673.9





ACTION CASE: BRAZIL

Leading the way to climatesmart urban planning in **Teresina**

Latin America is the most urbanized region in the world. While just over half of the world's population lives in cities, in Latin America that number is over 80 per cent and growing (Ezquiaga Arquitectura, Sociedad y Territorio S.L., 2015), (Statista, 2023). Within Brazil, the northern state capital of Teresina is one of the most rapidly urbanizing cities, and is located in one of the poorest regions in the country (Parra, 2022). Ensuring that the livelihoods of the growing urban populations are safeguarded, including that people can enjoy the benefits of clean air, requires constant learning and innovation.

liveable and functional environment while continually expanding is challenging. In Teresina, rapid urbanization has occurred through unplanned horizontal expansion. Poorer populations, many of whom are new arrivals, have settled on the fringes, forming favelas (Espindola et al., 2017). Infrastructure to maintain and integrate the expansion is inadequate, resulting in increasing inequalities and higher poverty rates (UN-Habitat, 2021b). 10 Although the city's old title was Cidade Verde, Portuguese for green city, previous urbanization policies have resulted in green areas being replaced with grey infrastructure (Carneiro et al., 2021). This has magnified the temperature, increased air pollution, reduced the absorption of precipitation and increased river flooding, and thus exposed the population to higher rates of mosquito-borne diseases (Turmena and Maia, 2022).

Over the past decade, new local leadership and moreparticipatory forms of governance have unlocked a new approach to urban development. This has sought to integrate the city, utilize natural systems rather than combat them, and focus on improving the way inhabitants live together. This vision looked beyond the utilitarian functions of the city to one that encouraged innovation and polycentric decision-making. To ensure progress, new measurements and data have been collected and visualized in layered mapping, showing the interconnected nature of the different sectors (CARTO, n.d.). Although there are too many initiatives to describe, two stand out as being demonstrative of learning and innovation, and capable of providing numerous cobenefits.

As with many rapidly growing cities, maintaining a The first policy was to restore Teresina as a green city one that was in balance with its surroundings. The city put a moratorium on horizontal expansion, to enhance its capacity to absorb water from river flooding and rainfall and to do so in a manner that improves water quality. This was intended to rationalize infrastructure investment, intensify vertical development and preserve a green belt around the city that would allow for water run-off and cooling. An affordable housing programme was created to relocate vulnerable buildings, reduce exposure to flooding, make way for infrastructure improvements and address housing deficits.¹¹ The city also developed a storm-drainage system. Finding that it did not have sufficient public financing, the city developed public-private partnerships and used this with support from the World Bank to construct canals and decontaminate lagoons. It also reforested areas along the rivers and streams and incentivized further greening by implementing an urban tree-planting programme.

> To integrate the city while reducing costs and carbon emissions, steps were taken to modernize its public transportation system. Given that the intention was further integration, the city chose a participatory approach. This included forming 15 teams comprising public transport users to participate in 'open innovation', where they could provide recommendations to improve route planning and other recommendations for use by transportation planners (Euroclima, 2022). The city also diversified its transportation with three light-rail systems and the opening of 64 km of cycle lanes (Uchoa, n.d.). The transportation improved access to services, including health and education as well as employment (UN-Habitat, 2021b).

> The ability of Teresina to learn how to adapt to climate impacts while cleaning its air and lowering emissions has attracted support from within the country and internationally. Organizations ranging from the World Bank to the European Union and the United Nations have engaged with the city to support efforts to build resilience and raise standards of living for all. 12

¹⁰ Poverty incidence is estimated at around 47 per cent in Teresina (UN-Habitat, 2021b).

¹¹ Teresina adopted a major policy - Urban Perimeter Act - in 2015 for freezing the urban perimeter

¹² UN Habitat has developed a Climate Resilience Profiling Tool to provide a strategic action plans for cities. This tool is used in conjunction with the City Resilience Global Programme (CRGP) to address issues such as climate change and sustainable urban planning and development (UN-Habitat, 2021a).




Resilience deficit 8. Increasing flood risk and urbanization


Map 10. Percentage of urban population living in slums (latest value since 2006), increase in urban damage between 2010 and 2030 relative to the 2010 values under the SSP2 RCP4.5 scenario, for flood with a return period of 100 years and projected relative change in urban population between 2022 and 2050 (SDG indicator 11.1.1)

Flooding is one of the costliest metrological hazards, causing hundreds of billions of dollars of damage annually (Ward et al., 2013). Although the impacts of climate change on riverine and urban flooding vary (Alifu et al., 2022), with some areas expected to receive more rain and others less (IPCC, 2021a), the overall increase in the intensity of rains increases flood risk, particularly in south Asia, south-east Asia and the western Amazon (Eccles et al., 2019). The population in slums and unplanned urban settlements is projected to double by 2050, an increase of 100 per cent from 760 million in 2022 to 1570 million in 2050 (Arnell and Gosling, 2016).

Map 10 shows that without rapid action to address this resilience deficit, many of these already vulnerable people will be also exposed to significantly higher flood risk

Urban areas, where most of the world's population lives, will be particularly vulnerable, given the inability of urban surfaces to absorb rain (Hettiarachchi et al., n.d.). In some regions, such as Europe, direct damage due to flooding is expected to increase sixfold without climate change adaptation and risk reduction, with losses per square metre being the highest in urban areas (European Commission, 2020). Map 10 shows the projected damage to urban areas due to riverine flooding based on urban-population growth rate. The map also shows the correlation between poor infrastructure vulnerable to riverine flooding and the preponderance of urban slums.





The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.10 Jun 2023



ACTION CASE: THE EUROPEAN UNION:

Integrating climate risk data into the broader risk management system

and storm surges. To create a fuller appreciation of complex systems of understanding of risk and resilience. These tools are intended to build foresight into policymember states in both urban and rural areas.

analytical tools based on integrating data from national standards.

As information is only as good as how it is utilized, the efforts to become climate-neutral by 2050. European Commission and the European Environment Agency created a common analytical platform called the

Despite being in a high-income region, European Climate Adaptation Platform (Climate-ADAPT). Climate-Union member states face numerous threats due to ADAPT provides a set of analytical tools capable of earthquakes, biodiversity loss, as well as climate threats measuring current and future vulnerabilities of regions including wildfires, heatwaves, floods, sea-level rise and sectors and proposing adaptation strategies and actions. Among the instruments are the Risk Data climate-exacerbated risks, the European Commission is Hub, which pulls together national datasets, and the developing increasingly sophisticated policy instruments Resiliency Dashboard, which provides data on multito assist its member states in collectively fostering dimensional risks based on the main threats or megatrends. Collectively, these efforts work to socialize and harmonize metrics so that European Union member making and enhance the anticipatory governance of EU states have the information needed to develop moreeffective policies to absorb and respond to shocks.

This system is evidence-based, premised on building Drawing from these resources, the European Commission was able to develop and adopt a strategy statistics sources. To ensure this system of data to adapt to the unavoidable impacts of climate change gathering and integration is harmonized among its and other threats by developing resilience in all sectors member states, in 2021, the European Commission by 2050. Specifically, the strategy recalls the importance conducted a climate-impact assessment to identify of ensuring that climate actions are informed by robust and address gaps in data-gathering methodologies and data and common risk-assessment tools. To ensure synergies with mitigation, this strategy is closely connected with, and contributes to, European Union

The case of Greece

One European Union member state that is utilizing these Although Greece often suffers from dry and hot is implementing 106 investment measures and 68 of this plan is to accelerate the transition to a lowcarbon resilient economy. Using the systems analysis of these tools, the plan has identified a multitude of projects across interrelated sectors. These range from reforestation to flood mitigation, irrigation networks, waste management and environmental protection, as well as reforms to its legal and regulatory frameworks to improve transportation, education, health, digitization and redesigning the labour market to fuel, and benefit from, the transition.

tools and the resources flowing from the European summers, these conditions are often interspersed by Commission adaptation strategy is Greece. In 2021, rapid flooding causing death, injury and destruction of Greece adopted its own Recovery and Resiliency infrastructure. To protect its people and rich heritage, the Plan, which, with European Union financial support, government utilized a mix of loans, grants and national financing to upgrade its infrastructure, improving reforms, at a cost of €30 billion. One of the mains aims drainage and expanding natural water sinks. These investments will save money and lives, and ensure that its heritage sites are protected.




Resilience deficit 9. Increasing heat and poverty

Map 11. Percentage of work hours lost due to heat stress in 2025 and increase in the work hours lost due to heat stress between 2025 and 2055, relative to the 2025 values, for RCP 2.6 and RCP 6.0 scenarios (SDG indicators 8.2.1 and 1.1.1)


Note: RCP = Representative concentration pathway.


Working under the right conditions is important for rising as temperatures increase, with expectations that productivity, health and well-being. When temperatures economic losses will reach \$2,400 billion in 2030. This rise above 26°C, labour productivity begins to decline. is 2.2 per cent of total working hours worldwide - a loss At 34°C, productivity drops by 50 per cent. In 1995, the equivalent to 80 million full-time jobs (International Labour economic loss due to heat stress at work was \$280 billion Organization, 2019). (International Labour Organization, 2019). That figure is

RCP 2.6 scenario



RCP 6.0 scenario





The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations. Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).





Map 12 Increase in the percentage of work hours lost due to heat stress between 2025 and 2055 for RCP 2.6 and RCP 6.0 scenarios, and proportion of population living below the international poverty line (latest values since 2015)

Note: RCP = Representative concentration pathway.

The impact of heat is inherently inequitable. Lower- and middle-income countries are affected the most, and those working in hard labour, primarily agriculture workers, are affected the worst, as shown in Map 11. This trend correlates strongly with poverty rates. Such inequities will increase over time without mitigative measures. As illustrated in Map 12, the loss of working hours due to heat contributes to higher poverty.

RCP 2.6 scenario





UNITED NATIONS Geospatial Map No. 4673.12b Jun 2023

Key figures



60% Percentage of loss in the agricultural sector out of total working hours, projected to be lost due to heat by 2030 (International Labour Organization, 2019)



80 million This is 2.2 per cent of total working hours worldwide – a loss equivalent to 80 million full-time jobs (International Labour Organization, 2019)



5.3% and 4.8% Loss of working hours in south-east Asia and West Africa by 2030 due to heat stress (International Labour Organization, 2019)



49% vs 10% `Percentage of labour loss in Africa compared to in the Americas under a scenario of 3.0°C warming (Dasgupta et al., 2021)

The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).



Action case: Maldives

Strengthening resilience through economic diversification

its achievements. To consolidate gains and increase its resilience, including against rising temperatures, Maldives embarked on a diversification strategy across all major sectors, including its economy, and its electricity and water systems.

Situated in a remote region of the Indian Ocean, with its communities separated over hundreds of coral islands, life in Maldives is dependent on, and exposed to the has implemented new climate-resilient IWRM systems forces of nature. To develop its economy and allow on four main islands, that combine rainwater harvesting its population to reach the level of affluency of other with desalination and water-rationalization interventions. nations, Maldives embarked on a development strategy that focused largely on tourism, and an energy system that relied on fuel imports. This resulted in it achieving upper middle-income status according to the World Bank, and in raising the standard of living for its citizens (World Bank, 2023).

However, the COVID-19 pandemic and slow-onset environmental pressures have revealed vulnerabilities. Maldives experienced a 33 per cent economic contraction during the pandemic. Hazards related to diminishing freshwater reserves, cyclones and sea-level rise threatened to undermine the country's advances (Asian Development Bank, 2020a). The government response was to create recovery programmes that encouraged economic diversification, collaboration and innovation.

To diversify its economy away from tourism, Maldives has shifted investments to the 'Blue Economy'

A crisis often brings opportunity and a chance to to modernize its fishing industry, improving the capacity change course. This is the case with Maldives, which, to refine its products. It has banned the use of fishing after making impressive development gains, found nets13 and expanded marine-protection areas, which that its reliance on tourism for growth, in combination now cover 543 km2 (Ministry of Environment, Climate with environmental pressures, threatened to undermine Change and Technology, Republic of Maldives, 2022a). Also, starting in 2023, all single-use plastics have been banned (PSM News, 2023). These measures help make the economy more resilient while also protecting the coastal ecosystems, providing a buffer against storms and tidal surges.14

> To address chronic water shortages, the government has diversified and decentralized water management. It Improvements are being made to recycle wastewater, with dozens of water-treatment plants constructed on the islands (World Bank, 2019). It has also increased water storage and developed water-security plans for the event of water shortages. These policies improve access to clean water and allow the groundwater to recharge, thus improving ecosystems and reducing pollution, while also reducing costs related to water management (UNDP Climate, 2022).

Maldives is investing in renewable energy to enhance the resilience of its electrical system. In December 2022, the country opened its first 5 MW solar facility outside the capital as part of a programme to develop 50 MW of solar and battery capacity, supported by the World Bank. The innovative financing framework utilized for this project may be used as a model in other small island developing States, including Mauritius and Seychelles (Chen et al., 2023). Maldives is also expanding rooftop solar capacities, which increased from 1.5 MW to 21.5 (sustainable use of ocean resources). It has taken steps MW between 2009 and 2019 (Ministry of Environment,

Climate Change and Technology, Republic of Maldives, 2022b). To improve grid stability, high-voltage connections are being built between the islands.15 These efforts improve resilience and are also costeffective by reducing expenditure on expensive fuel imports. Energy transition is also central to achieving the country's ambition to become net zero by 2030.

The combination of these diverse set of interventions marks a turning point for Maldives, moving it away from reacting to emergencies to more sustainable, longerterm solutions.



[The Maldives is] moving away from reacting to emergencies to more sustainable,

longer-term solutions.

13 Fishing accounts for 90% of the country's exports. (Ministry of Fisheries, Marine Resources and Agriculture, 2019).

14 The Maldives Ministry of Environment is implementing the Coastal Protection Projects.

15 Interconnection of the power grids: Hulh (Asian Development Bank, 2020b) (phase 1 in 2021) and Male'–Villingili–Gulhifalhu–Th

Resilience deficit 10. Risk of climate change to coastal infrastructure

Map 13. Increased exposure of the top-100 global container ports to extreme sea levels (ESLs): projected change of the return period (Tr) of the baseline 1-in-100 years extreme sea level (ESL100) under different global-warming scenarios (i.e. 1.5°C, 2°C SWLs). (SDG 1.5, 9.1, 9.a, 13)


With over 80 per cent of the volume of global trade in goods carried by sea, seaports are key nodes in the network of global supply chains, providing critical access to global markets (Verschuur et al., 2022) as well as the ocean economy, and vital to trade and development (Asariotis, 2021). At the same time, these complex infrastructure assets, often integrated within large urban agglomerations, are at the frontline of climate change (Izaguirre et al., 2020). Related impacts can result in significant damage, as well as costly disruption and delay across supply chains, with potentially far-reaching consequences for international trade and the sustainabledevelopment prospects of the most vulnerable nations, including SIDS, that depend on their seaports as lifelines for trade, energy, food, tourism and in the context of DRR (Asariotis, 2020). Global port-specific risk from natural hazards has been estimated at US\$ 7.5 billion per year, with 32 per cent of the risk attributed to tropical cyclone impacts, and an additional US\$ 63.1 billion of trade estimated to be at risk (Verschuur et al., 2023). However, a single extreme event can cause much higher losses, such as Hurricane Sandy (2012) which caused over US\$ 60 billion losses (Strauss et al., 2021), including extensive damage and a week-long shut-down of the US New York/ New Jersey container port (Strunsky, 2013).

Under increased global warming, seaports will be exposed to rising mean and, particularly, extreme sea levels (ESLs) that could overwhelm their current defences and lead to extensive flooding and operational disruptions. Port defences are designed to withstand extreme events with a certain return period, commonly the 1-in-100 years ESL (ESL100) estimated at the time of design or construction. However, ESLs of a magnitude so far expected to occur once a century (ESL100), will occur much more often under climate change.

Map 13 shows the evolution of the return period for the baseline (mean of the 1980 – 2014 period) 1-in-100 years extreme sea level (ESL100) under different global-warming scenarios, at the top-100 global container ports.

With maritime trade expected to triple by 2050 (ITF, 2019) and climate-driven hazards expected to increase, significant acceleration of investment in climate change

adaptation and resilience-building for ports is needed to avert, minimize and address damages or losses and safeguard supply chains. Major scaling-up of affordable investment in infrastructure adaptation will be critical for developing countries (United Nations Conference on Trade and Development, 2022b), particularly vulnerable SIDS that are sea-locked and therefore depend particularly on their ports and airports. The case study below on Jamaica and Saint Lucia demonstrates that key coastal transport-infrastructure assets in these countries are at a high and growing risk of coastal flooding and operational disruptions, as early as in the 2030s, in the absence of adaptation measures.



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

Key figures



38% Global container port activity occurring in areas of high hurricane risk between 1980 and 2020 (Notteboom et al., 2019)

0.6 to 1.1 metres Projected average

sea-level rise by 2100 (IPCC, 2021a)




4.7% Increase in carbon emissions due to shipping between 2020 and 2021 (United Nations Conference on Trade and Development, 2022a)



\$6.9 trillion a year Global investment needed in infrastructure to meet SDGs (OECD et al., 2018)

2.0°C Specific Warming Level



UNITED NATIONS Geospatial Map No. 4673 13a UNITED NATIONS Geospatial Map No. 4673.13b



ACTION CASE: JAMAICA AND SAINT LUCIA

Safeguarding ports with long-term investment

effects of climate change, as are the costs associated 2017a) and 2 per cent in Saint Lucia (UNCTAD, 2017b). These costs are due primarily to the interruption of operations at the ports and airports in the country, but economic growth. also to damage caused to infrastructure (Monioudi et al., 2018).

strengthen and sea levels rise. This creates additional risks to ports and airports, as well as the surrounding network of rail, roads and industrial complexes. Jamaica fund the multi-year and multi-million-dollar investments

Located in what is often termed 'hurricane alley', and Saint Lucia have two main airports and two main Jamaica and Saint Lucia are no strangers to flooding and seaports. These installations are on or near the coast hurricanes. These weather patterns are, unfortunately, and are generally 1-2 metres above sea level. As island expected to gradually intensify due to the slow-onset nations, both countries are aware of the threats posed by climate change to their air and sea transportation with these impacts (IPCC, 2021c). Studies indicate that systems, and both have developed long-term plans and economic losses due to storms and floods amount to governance structures to solicit investments to upgrade approximately 7 per cent of GDP in Jamaica (UNCTAD, their transportation networks. These upgrades are critical to offsetting the steadily increasing pressures caused by climate change, and key to generating

Jamaica's Kingston Container Terminal is one of the largest ports in the Caribbean and is the country's As climate change heats the oceans, tropical storms largest employer. Ensuring that the port is constantly upgraded to improve resilience is part of the national Climate Change Policy Framework (UNCTAD, 2017a). To

both have developed long-term plans and governance structures to solicit investments to upgrade their transportation networks.

These upgrades are critical to offsetting the steadily increasing pressures caused by climate change, and key to generating economic growth.

required, Jamaica has blended loans from the InterAmerican Development Bank and other partners, with private investments, outsourcing the work to private holding companies (Feller, 2019). Similarly, Saint Lucia has included support to its ports in its national adaption plan (Government of Saint Lucia, 2018), soliciting a similar array of financing to upgrade the capacities of its main seaport, Castries, to receive cargo and cruise ships (Pate, 2022).

Managing slow-onset variables, such as those faced by island nations from storms and flooding, requires longterm vision and sustainable financing. The investments made in Jamaica and Saint Lucia will create wealth and will also reduce risks to infrastructure and supply chains.

Extreme shocks and cascading impacts

Map 14. Percentage of population in poverty (<\$1.9 per day) in 2019 and increase between 2019 and 2022 (SDG indicators 1.1.1 and 8.5.2)

Disasters occur only when a lack of resilience allows systems to be overwhelmed. As hazard events become more frequent and more intense due to climate change, efforts to build resilience and reduce existing risk, while avoiding the creation of new risk, need to be accelerated. Given the frequency and overlapping nature of events, even relatively small but frequent events can have an outsized impact if countries do not have the opportunity to recover and restore their systems.

While most disaster-related losses are due to smaller and medium-sized events, infrequent high-impact shocks can wipe out decades of sustainable gains in a short period in areas with high levels of resilience deficits. As such, it is also important to plan and act to prevent the potential impacts of lower-frequency, high-impact events. When, unfortunately, events like the COVID-19 pandemic do occur, it is essential to understand what went wrong, and how impacts cascaded across systems to undermine sustainable development. This lesson can help inform future action to better prevent and prepare for future similar hazard events.

Between 2019 and 2022, poverty rates increased globally by 8 per cent, pushing an additional 54 million people into poverty. The countries that experienced the highest rise in poverty rates are illustrated in Map 14. COVID-19 resulted in economic losses, many of which disproportionately affect the most vulnerable people.


Key figures



6.2 million Deaths directly attributable to COVID-19 (WHO, 2023).



70 million Number of persons that fell into extreme poverty in 2020 due primarily to COVID-19 (the global extreme poverty rate of 8.4% in 2019 increased to 9.3% in 2020) (World Bank, 2022b)



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.


A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.14 Jun 2023



Map 15: Change in female unemployment between 2019 and 2022 relative to the 2019 values and ratio between female and male unemployment rates between 2019 and 2022 (SDG indicators 1.1.1 and 8.5.2)

As seen in Map 15, between 2019 and 2020, women's employment levels fell by 4.2 per cent compared to 3 per cent for men (ILO, 2021). In a study of 58 countries, women living with children were more likely to lose their jobs than men living with children (29 per cent compared to 20 per cent) (UN Women, 2021b) (UN Women, 2021a). The long-term impact is that progress to achieve SDG targets on gender equality has significantly regressed, with some reports stating that 40 years were lost (World Economic Forum, 2021a).



The boundaries and names shown and the designations used on this map do not imply official endorsement or acceptance by the United Nations.

Dotted line represents approximately the Line of Control in Jammu and Kashmir agreed upon by India and Pakistan. The final status of Jammu and Kashmir has not yet been agreed upon by the parties. Final boundary between the Republic of Sudan and the Republic of South Sudan has not yet been determined.

A dispute exists between the Governments of Argentina and the United Kingdom of Great Britain and Northern Ireland concerning sovereignty over the Falkland Islands (Malvinas).

UNITED NATIONS Geospatial Map No. 4673.15 Jun 2023

Key figures



135 Years Years expected to close the gender-inequality gap from 2021 (World Economic Forum, 2021b)




43% Percentage of women employed compared to 69% of men in 2021 (ILO, 2021)



3. HOW TO BUILD A MORE RESILIENT FUTURE

Taking action to address resilience deficits in a rapidly changing world is challenging, but not impossible. The action cases included in this report are examples of positive resilience-building in action. Figure 4 illustrates pathways to making sustainable development choices.

Figure 4. Pathways to making sustainable development choices



Source: Adapted from (IPBES, 2021)


resilient.

echoed these same themes, while the IPCC Report of the same year also highlighted the importance of resilient sustainable development, and expanded on key themes. Resilience can be seen as a key connector between climate change, disaster risk reduction and sustainabledevelopment action. The experience gained though action now is also essential to improving foresight capacity, and to fostering more-collaborative, participatory processes, and an agile and anticipatory style of governance that will be essential for a volatile climate future (UNDP

In 2020, UNDP Common Guidance on Helping Build Global Centre for Public Service Excellence, 2018). The Resilient Societies, highlighted the four key elements, in action cases in this report highlight that countries and Figure 5 below, that help make sustainable development communities are already applying these elements in their policies and actions to build a more resilient future.

In 2022, the Global Assessment Report of UNDRR Figure 5 summarises how key elements of sustainable development need to include understanding risk, recognising systems are interconnected, including stakeholders and building capacities for resilience.

Figure 5. Elements of sustainable development



Source: Adapted from (United Nations, 2020)

Table 2. Summary of key resilience elements and related action cases

Key UN guidance/ IPCC element	Why it matters	Relevant action case examples from the report
3.1 Understand the risk and context	Understanding risk is the bedrock priority of the Sendai Framework, from which other actions stem.	All
3.1.1 Understand who and what is vulnerable and why	When developing a strategy, who needs resilience, and from what, are the first questions to ask? In answering, it is important to understand how changes in one system affect other systems, so the integrity of the whole can be addressed (United Nations, 2020).	Fiji Yemen
3.2 Recognize systems are interconnected	Understanding how systems are interconnected is important in deciding what type of strategy is needed and where to prioritize investments. Given that the impacts of climate change increase over time, this requires a capacity to understand how slow-onset feedback affects already complex systems (United Nations, 2020).	All
3.2.1 Foster complex system understanding	Although systems are interlinked, each actor has its own set of needs and thinking patterns that dictate how they interact and affect other elements within the same system. Using a complex-systems approach is a way to move beyond reductionist thinking, to appreciate the integrity of the system as a whole. Doing so allows policymakers to anticipate the range of impacts and to avoid inadvertent maladaptive interventions.	European Union Yemen
3.2.2. Manage connectivity	Connectivity refers to the way different components within a system interact. This connectivity can either be a source of risk or a source of resilience. For example, a family network can help its members through difficult times but, as experienced during the COVID-19 pandemic, the same interaction can contribute to spreading the disease. Socially, connectivity can build cohesion and help build trust, and bring different insights and perspectives. However, too much homogeneity can lower innovation and critical reasoning.	Barbados Jamaica and S Lucia
3.2.3 Manage slow variables and feedbacks	Slow-onset variables and feedback accumulate in natural systems gradually, increasing exposure to threats. For instance, increasing temperatures may slowly reduce the productivity of certain types of crops, leading to more food insecurity. Deciding how to intervene to modify slow-onset processes requires an understanding of how they are changing and why.	Great Green Wa

3.2.4

Maintain diversity and redundancy

In nature, diversity and redundancy are critical to resilience. That a diversity of species performs the same or similar functions means that when one species is no longer able to function, the others fill in the gap. In human systems, the concept of redundancy is often avoided, to reduce costs. However, as seen in the examples, maintaining diversity can significantly European Union improve resilience in multiple sectors, from water to energy.

3.3

Include multiple stakeholders

Including multiple stakeholders increases resilience as it allows more All people to participate, thus mobilizing society to take collective action to protect itself from common risks. Broadening participation requires more time and resources, but the intervention that is decided upon will have greater buy-in and the chances of it being sustainable will have improved (United Nations, 2020).

3.3.1

Broaden participation Broadening participation expands the scope of knowledge and builds Brazil legitimacy. It ensures information circulates through the system and maintains cohesion and unity of purpose. As creating constructive participation can often be time-consuming, it requires adequate preparation to harness the positive aspects of broadening participation.

India

3.4

Build skills and capacity for resilience

The capacity of people and systems to withstand and adapt to shocks All can be improved if the following three methods are pursued in parallel: facilitating learning and experimentation, building diversity and redundancy so several actors can perform the same or similar functions, and ensuring all actors are working collaboratively to address a common set of challenges (United Nations, 2020).

3.4.1

Encourage learning and experimentation

Adaptive management and learning are vital to maintaining the versatility Brazil needed to navigate through volatile, uncertain and changing circumstances. Optimizing performance requires continual testing and adapting of approaches based on impact and experience.

3.4.2

Foster flexible and connected 'polycentric' governance

Polycentric governance occurs when several actors operate together to Indonesia address a common set of problems. This capacity to work collaboratively requires the actors to operate under a common set of norms and rules. This element complements the other elements as it allows for greater diversity and participation to be utilized effectively.

4. CONCLUSIONS:


The SDG indicators were established to unify and broaden the way the world measures progress towards sustainable development. As demonstrated in this report, they can also be useful in understanding the interconnectedness of people, the planet and prosperity, and the importance of building resilience across these systems.

The SDG indicators are also a way to move beyond with other pressures, including degrading planetary viewing progress as simply a matter of growth in GDP. health, conflict and other hazards, to create compound Although GDP is a useful reference for the size and risks that undermine the sustainability of achievements growth of an economy, it is not an accurate measure made in global development. of what makes life worthwhile. While GDP measures the level of consumption, it does not show how. These compound or layered hazards have a higher growth affects the standard of living or if development aggregate impact than if they were to occur separately. is sustainable. And even though it shows average Moreover, the speed at which they occur erodes earnings, it does not consider how those earnings are resilience, as systems are not afforded the time to distributed within a society.

as the global temperature surpasses 1.5°C above natural ecosystems. pre-industrial levels. Figure 6 shows the generational impacts of climate change. These impacts will combine

recover. If humanity is to continue to progress and achieve the desired development objectives, a more The speed and scale of climate-change impacts on holistic approach is required that balances human planetary, human and economic health will accelerate progress with the need to maintain the integrity of

Figure 6: Generational impacts of climate change



Source: IPCC AR6 (IPCC, 2023)

Failing to recognize and address resilience deficits holds back sustainable-development progress and risks reversing the progress achieved so far. Making risk-informed choices is essential to set countries on a more sustainable future path – one that is adapted to the volatile climate future and which can prevent and better manage disasters and potential future polycrises. Therefore, key lessons from this report are the following:

- To avoid intensification of the current polycrisis, urgent action is required to curtail greenhouse gas emissions and to build resilience to the shocks and hazards that are curtailing sustainable development.
- Action to build resilience is possible and can accelerate achievement of current sustainabledevelopment targets in a way that safeguards people, the planet and future prosperity.

- The SDG indicator framework is not just a set of development objectives. The indicators can also be utilized as a tool to identify and quantify resilience deficits and the counterposed accelerator action that can build resilient sustainable development despite the complex future.
- Using existing data for the kind of analysis included in this report's maps can help ensure that climate adaptation and building resilience is holistic and contributes towards the future well-being of people, the planet and the economy. Identifying resilience deficits also helps policymakers move beyond using only economic growth as the primary indicator of progress.
- Improving the accessibility and quality of hazard and SDG-progress data can make a cost-effective contribution to improved risk management and climate change adaptation decision-making.

Utilizing SDG indicators as a tool to identify resilience deficits that are hindering target achievement is helpful, because of their broad scope and because the metrics and processes to collect the data are already in place.

- Investing earlier in resilience and adaptation can avoid costs of hazard impacts, and save lives and money. Replacing destroyed crops, infrastructure and electricity transmission networks costs more than preventing disasters in the first place.
- Striking a balance between the needs of people, the planet and prosperity is not just a desirable goal, but a fundamental requirement. The pursuit of human development must be recalibrated to not only maintain the integrity of ecosystems, but also to restore them. Doing so requires a reexamination of what is required for sustainability. The metric of perpetual economic growth must be expanded to include the broader interests of society and rebalanced to include the costs and benefits affecting natural ecosystems.

Measuring what is valued reflects societal norms and provides the basis for the policies to follow. Looking beyond 2030, increased recognition in emerging international systems of the need to balance the resilience of people, the planet and prosperity will be essential for current and future generations.

Methodology and sources

The maps included in the report represent an inter-agency effort to assess current and projected resilience deficits towards the achievement of the SDGs. The maps are the result of collaboration between UNDRR, the GEM Foundation, the United Nations Agencies that are custodians for the Sustainable Development Goals (SDGs) Indicators depicted in the maps, and institutions who conduct research on the topics addressed in this report.

Each map showcases country values of one specific SDG indicator and one or multiple risk drivers, such as natural hazards like heat, flood or drought, or demographic or urbanization trends, that create resilience deficits. Where possible, the maps also show future projections of these resilience deficits under various climate scenarios, based on IPCC greenhouse-gas-emission-rate scenarios, representative concentration pathways (RCPs) or considering different global warming levels.

Map 1

SDG	Variable	Year	Source
1.5.1, 11.5.1 and 13.1.1	Number of directly affected persons attributed to disasters per 100,000 population (number)	2005-2021	SDG Portal
	Countries that reported having MHEWS (multi- hazard early-warning systems)	2022	Target G report, UNDRR

The number of directly affected persons represented in the map corresponds to the average number of directly affected persons attributed to disasters per 100,000 population between 2005 and 2021. The data used to calculate the average values is available on the SDG Portal (United Nations, 2023a)

The information relative to the countries that reported having MHEWS is available in section 2 of UNDRR's Target G report (UNDRR, 2022a)

Map 2

SDG	Variable	Year	Source
1.5.1, 11.5.1 and 13.1.1	Number of directly affected persons attributed to disasters per 100,000 population (number)	2005-2021	SDG Portal
	Relative change in total population between 2022 and 2050 (%)	2022	United Nations, Department of Economic and Social Affairs, Population Division (2022). Probabilistic Population Projections based on the World Population Prospects 2022

The number of directly affected persons represented in the map corresponds to the average number of directly affected persons attributed to disasters per 100,000 population between 2005 and 2021. The data used to calculate the average values is available on the SDG Portal (United Nations, 2023a).

The values of the relative change in total population use the median (50 per cent) prediction interval of the probabilistic projections of total population by country from the World Population Prospects 2022 (United Nations, 2022b). The values represented in the map were calculated as follows:

$$\frac{(Pop_{2050} - Pop_{2022})}{Pop_{2022}} \times 100$$

Map 3 and 4

SDG	Variable	Year	Source
2.1.2	SDG Portal	3-year average: 2019-2021	FAOSTAT
	Percentage of country area exposed to drought frequency increase (%)	2021	GAR SR on Drought 2021

The values for the prevalence of moderate or severe food insecurity are available on the FAOSTAT website (FAO, 2022a).

The percentage of country area exposed to drought frequency increase was calculated based on the GAR SR on Drought 2021 Figure 1.3 data. This figure shows the "Change in meteorological drought frequency (events/decade) from recent past (1981–2010) to 2100 for four projected warming levels of global surface air temperature." As stated in the report, "The projections indicate the global temperature increase from pre-industrial values (1881–1910). GWLs are reached during slightly varying time windows, depending on the climate simulation." In these maps, the lower GWL (1.5°C and 2°C) scenarios are presented, as these are explicitly included as targets in the Paris Agreement and their "time windows are centred approximately in the years 2025 and 2040 (median values from all combinations of global circulation models and regional circulation models)". The complete dataset covers the entire planet in a gridded format. This dataset was filtered by selecting only the positive values, which represent an increase in the meteorological drought frequency. For each country, the area covered by these grid points was measured and compared with the total country area, to calculate the metric presented in the map: the percentage of country area exposed to drought frequency increase.

Map 5

SDG	Variable	Year	Source
4.6.1	Youth literacy rate (%)	Latest value since 2014	UNESCO Institute for Statistics
	Estimated number of internal displaced children (under 18) at the end of 2022 (number)	2022	Internal Displacement Monitoring Centre (IDMC). Global Internal Displacement Database Data (2023)

The data on youth literacy rate was retrieved from the Children's Climate and Environment Risk Index (CCRI) methodology, which was developed and shared by UNICEF. As mentioned in CCRI, the source of this data, used both in CCRI and in this report, is UNESCO Institute for Statistics.

The number of internal displaced children (under 18) values correspond to the sex and age disaggregated data (SADD) of the total number of internally displaced persons (IDPs), available at the Global Internal Displacement Database of the Internal Displacement Monitoring Centre (Internal Displacement Monitoring Centre, 2023). The definition of total number of IDPs is presented in the methodological notes of the data: "Represents the total number of internally displaced persons (IDPs), in a given location at a specific point in time. It could be understood as the total number of people living in a situation of displacement as of the end of the reporting year." The same methodological notes explain how the SADD estimates are derived: "Sex and age disaggregated data (SADD) for displacement associated with conflict or disasters is often scarce. One way to estimate it is to use SADD available at the national level. IDMC employs United Nations population estimates and projections to break down the number of internally displaced people by sex and age." For more information read the methodological notes at (Internal Displacement Monitoring Centre (IDMC), 2023).

Map 6

SDG	Variable	Year	Source
6.4.2	Level of water stress: freshwater withdrawal as a proportion of available freshwater resources (%)	2020	SDG Portal
	Relative change in total population between 2022 and 2050 (%)	2022	United Nations, Department of Economic and Social Affairs, Population Division (2022). Probabilistic Population Projections based on the World Population Prospects 2022

The level of water stress relative to 2020 is available on the SDG Portal (United Nations, 2023a).

The values of the relative change in total population use the median (50 per cent) prediction interval of the probabilistic projections of total population by country from the World Population Prospects 2022 (United Nations, 2022b). The values represented in the map were calculated as follows:

$$\frac{(Pop_{2050} - Pop_{2022})}{Pop_{2022}} \times 100$$

Map 7

SDG	Variable	Year	Source
15.3.1	Proportion of land that is degraded over total land area (%)	2019	SDG Portal
15.5.1	Red List Index	2020	SDG Portal and IUCN. 2022. The IUCN Red List of Threatened Species. Version 2022-2. https://www. iucnredlist.org.

The two indicators used in map 7 are available on the SDG Portal (United Nations, 2023a). The proportion of land that is degraded is relative to 2019, while the Red List Index values correspond to 2020.

Map 8

SDG	Variable	Year	Source
7.2.1	Share of modern renewables in the total energy consumption (%)	2020	IEA (2022), World Energy Balances;
			Energy Balances 2020, United Nations, New York, 2022;
			Energy Statistics Database 2020, United Nations, New York, 2022
7.3.1	Energy efficiency (megajoules per USD constant 2017 PPP GDP)	2020	IEA (2022), World Energy Balances
			Energy Balances 2020, United Nations, New York, 2022.
			Energy Statistics Database 2020, United Nations, New York, 2022

Mean near surface air temperature under a 2°C 2021 warming scenario SSP2-4.5 (°C)

IPCC WGI Interactive Atlas: Gutiérrez, J.M., R.G. Jones, G.T. Narisma, L.M. Alves, M. Amjad, I.V. Gorodetskaya, M. Grose, N.A.B. Klutse, S. Krakovska, J. Li, D. Martínez-Castro, L.O. Mearns, S.H. Mernild, T. Ngo-Duc, B. van den Hurk, and J.-H. Yoon, 2021: Atlas. In Climate Change 2021: The Physical Science Basis. Contribution of Working Group I to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change [Masson-Delmotte, V., P. Zhai, A. Pirani, S.L. Connors. C. Péan. S. Berger, N. Caud, Y. Chen, L.Goldfarb, M.I. Gomis, M. Huang, K. Leitzell, E. Lonnoy, J.B.R. Matthews, T.K.Maycock, T. Waterfield, O. Yelekçi, R. Yu, and B. Zhou (eds.)]. Cambridge University Press. In Press. Interactive Atlas available from Available from http:// interactive-atlas.ipcc.ch/

The data on share of modern renewables and energy efficiency was provided by IEA (World Energy Balances) and United Nations (Energy Balances 2020 and Energy Statistics Database 2020).

The values of the mean near surface air temperature are available on the IPCC WGI Interactive Atlas (IPCC, n.d.b). The SSP2-4.5 scenario is commonly considered as the 'middle-of-the-road' intermediate GHG scenario, where CO2 emissions remain around current levels until the middle of the century, and start to decline after that, and socioeconomic factors follow their historic patterns.

Map 9

SDG	Variable	Year	Source
11.6.2	Annual mean levels of fine particulate matter (population-weighted), by location (micrograms per cubic metre)	2019	SDG Portal
	Ambient air pollution attributable death rate (per 100 000 population, age-standardized)	2019	WHO

Data on ambient air pollution attributable death rate is available on the Global Health Observatory of WHO (World Health Organization, 2023b), while the annual mean levels of fine particulate matter can be accessed from the SDG Portal (United Nations, 2023a).

Map 10

SDG	Variable	Year	Source
11.1.1	Proportion of urban population living in slum households (%)	Latest value since 2006	UN Habitat Urban Indicators Database
	Increase in the urban damage between 2010 and 2030 relative to the 2010 values under the SSP2 RCP4.5 scenario, for flood with a return period of 100 years (%)	2015	Aqueduct Global Flood Risk Maps, WRI (World Resources Institute)
	Relative change in urban population from 2022 to 2050 (%)	2018	United Nations, Department of Economic and Social Affairs, Population Division (2018). World Urbanization Prospects: The 2018 Revision, Online Edition.

The proportion of urban population living in slum households is available on the UN Habitat Urban Indicators Database (UN Habitat, 2021) and corresponds to the latest value since 2006.

The data for urban damage comes from the Aqueduct Global Flood Risk Maps of the WRI Institute (Luo, 2015), which provides current and future river flood risk estimates in urban damage by country. The increase in urban damage was calculated as follows:

$$\frac{(Urban\ damage_{2030}-Urban\ damage_{2010})}{Urban\ damage_{2010}}\times 100$$

The values of urban damage for 2010 correspond to the baseline hydrological and socioeconomic scenarios, while the values for 2030 correspond to the SSP2 socioeconomic change and RCP 4.5 climate-change scenarios. As previously mentioned, the SSP2-4.5 scenario is commonly considered as the middle-of-the-road intermediate GHG scenario, where CO2 emissions remain around current levels until the middle of the century, and start to decline after that, and socioeconomic factors follow their historic patterns.

The values for relative change in urban population use the median (50 per cent) prediction of the urban population at mid-year by country from the World Urbanization Prospects 2018 revision (UN DESA, 2018). The values represented in the map were calculated as follows:

$$\frac{(UPop_{2050} - UPop_{2022})}{UPop_{2022}} \times 100$$

Map 11 and 12

SDG	Variable	Year	Source
1.1.1	Proportion of population living below the international poverty line (%)	Latest value since 2015	SDG Portal
	Increase in the % of work hours lost due to heat stress between 2025 and 2055 relative to the 2025 values (%)	2023	ILO 2019 Working on a Warmer Planet: The effect of heat stress on productivity and decent work
	Hours lost due to heat stress in 2025 (%)	2019	ILO 2019 Working on a Warmer Planet: The effect of heat stress on productivity and decent work
	Absolute increase in the % of work hours lost due to heat stress between 2025 and 2055 (%)	2019	ILO 2019 Working on a Warmer Planet: The effect of heat stress on productivity and decent work

The proportion of population living below the international poverty line is available on the SDG Portal (United Nations, 2023a), and corresponds to the latest value since 2015.

Data on the work hours lost due to heat stress was provided by ILO. The data includes estimates of working hours lost to heat stress by a healthy worker assumed to be working in the shade for a physical work intensity compatible with construction and agriculture (400W). The estimates are presented for two climate scenario pathways, RCP2.6 and RCP6.0, which, according to the ILO 2019 Working on a Warmer Planet report, "respectively predict temperature increases of 1.5°C and 2.7°C above pre-industrial levels by the end of the century. The RCP2.6 scenario entails vigorous climate action being taken today to decarbonize the economy and enhance carbon sinks, thereby limiting global warming to 1.5°C and effectively mitigating future climate change. The RCP6.0 scenario also involves mitigation, but of a weaker sort, so that global warming is limited only to 2.7°C."

Based on this data, increase in the percentage of work hours lost due to heat stress between 2025 and 2055 presented in map 11 was calculated as follows:

$$\frac{\left(\%\,Work\,\,hours\,\,lost_{2055} - \%\,Work\,\,hours\,\,lost_{2025}\right)}{\%\,Work\,\,hours\,\,lost_{2025}} \times 100$$

The absolute increase in the percentage of work hours lost due to heat stress, in map 12, corresponds to:

% Work hours
$$lost_{2055}$$
 – % Work hours $lost_{2025}$

A detailed explanation on how the percentages of working hours lost due to heat stress were estimated, including the climate data used in the analysis, can be found in Appendix I - Detailed Methodology of the Working on a Warmer Planet (International Labour Organization, 2019).

Map 13

SDG	Variable	Year	Source
	Seaport location	2019	World Port Index 2019
	ESLs ₁₀₀ projections for the global coastline	2018	EC-JRC data collection
	Port throughput for top 100 container ports (in million TEU)	2021	Lloyd's List

The datasets used in this map were provided by UNCTAD, and have the following sources: Data collation and treatment, Dr I Monioudi, University of the Aegean. Seaport location from World Port Index 2019 (National Geospatial-Intelligence Agency, 2019). ESLs₁₀₀ projections for the global coastline from EC-JRC data collection (European Commission, 2022); see also Vousdoukas et al., 2018 (Vousdoukas et al., 2018). Port throughput (in million TEU) for top 100 container ports in 2021 from (Lloyd's List, 2022)

Map 14 and 15

SDG	Variable	Year	Source
1.1.1	Percentage of population in poverty (<\$1.9 per day) in 2019 (%)	2022	Assessing COVID-19 impact on the Sustainable Development Goals - UNDP
1.1.1	Change in percentage of population in poverty between 2019 and 2022 relative to the 2019 values (%)	2022	Assessing COVID-19 impact on the Sustainable Development Goals - UNDP
8.5.2	Change in female unemployment between 2019 and 2022 relative to the 2019 values (%)	2022	ILO-modelled estimates
8.5.2	Ratio between female and male relative changes in unemployment rate between 2019 and 2022	2022	ILO-modelled estimates

The poverty values presented in this map were obtained from the UNDP study on Assessing COVID-19 impact on the Sustainable Development Goals, which "assesses the impact of three different COVID-19 scenarios on the SDGs, capturing the multi-dimensional effects of the pandemic over the next decades" (UNDP, 2022b). The change in percentage of population in poverty was calculated as follows, considering the COVID-19 scenario modelled in the report:

$$\frac{(PovertyPop_{2022} - PovertyPop_{2019})}{PovertyPop_{2019}} \times 100$$

The unemployment data is available on ILOSTAT (International Labour Organization, 2023), disaggregated by gender. The relative change in female unemployment (RCU_{female}) was obtained as follows:

$$RCU_{female} = \frac{(Female\ unemployment_{2022} - Female\ unemployment_{2019})}{Female\ unemployment_{2019}} \times 100$$

After calculating the RCU_{male} using the same formula as above, the ratio between female and male relative changes in unemployment, which is presented in the map, corresponds to:

 $\frac{RCU_{female}}{RCU_{male}}$

Abbreviations and acronyms

Acronyms

AR Assessment Report, published by the IPCC for each assessment cycle

CCRI Children's Climate Risk Index

COVID-19 coronavirus disease

CRGP City Resilience Global Programme

DRR disaster risk reduction

ESL Extreme Sea Level

ESRI Environmental Systems Research Institute

EWS Early warning system(s)

EW4All 'Early Warnings for All' initiative

FAO Food and Agriculture Organization of the United Nations

FAOSTAT Food and Agriculture Organization Corporate Statistical Database

FAQ frequently asked questions

FKDC Forum Komunikasi DAS Cidanau

GAR Global Assessment ReportGDP Gross Domestic ProductGEM Global Earthquake Model

GEO Group on Earth Observations

GGW Great Green Wall
GHG greenhouse gas

GWL Global Warming Level

HAP Heat Action Plan

IDMC Internal Displacement Monitoring Centre

IEA International Energy Agency

ILO International Labour Organization

IPBES Intergovernmental Science-Policy Platform on Biodiversity and Ecosystem Services

IPCC The Intergovernmental Panel on Climate Change

ITF International Transport Forum

IUCN International Union for Conservation of Nature and Natural Resources

IWRM Integrated water-resources management

JRC Joint Research Centre, European Commission

NASA National Aeronautics and Space Administration

NRDC Natural Resources Defense Council

MHEWS Multi-hazard early warning systems

MW megawatts

OCDE Organisation for Economic Co-operation and Development

ODI Overseas Development Institute

PES Payment for Environmental Services

PSM Public Service Media

RCP Representative Concentration Pathways

SADDsex and age disaggregated dataSDGSustainable Development GoalsSIDSsmall island developing States(s)SSPShared Socioeconomic Pathways

TEU twenty-foot equivalent unit

UN United Nations

UNDESA

UNCCD United Nations Convention to Combat Desertification
UNCTAD United Nations Conference on Trade and Development

UNDP United Nations Development Programme

UNDRR United Nations Office for Disaster Risk Reduction

UNEP United Nations Environment Programme

UNESCO United Nations Educational, Scientific and Cultural OrganizationUN-GGIM United Nations Global Geospatial Information Management

UN HABITAT United Nations Human Settlements ProgrammeUNHCR United Nations High Commissioner for Refugees

UNICEF United Nations Children's Fund

UN WOMEN United Nations Entity for Gender Equality and the Empowerment of Women

United Nations Department of Economic and Social Affairs

USA United States of AmericaWFP World Food Programme

WGI Working Group I

WHO World Health Organization

WMO World Meteorological Organization

WRI World Resources Institute

References

- Alessi, L., P. Benczur, F. Campolongo, J. Cariboni, A.R. Manca, B. Menyhert and A. Pagano. (2020). The resilience of EU member states to the financial and economic crisis. Social Indicators Research, vol. 148, pp. 569-598. Available at https://doi.org/10.1007/ s11205-019-02200-1
- Alifu, H., Y. Hirabayashi, Y. Imada and H. Shiogama. (2022). Enhancement of river flooding due to global warming. Scientific Reports, vol. 12. Available at https://www. nature.com/articles/s41598-022-25182-6
- Amaruzaman, S., D.T. Hoan, D. Catacutan, B. Leimona and M. Malesu. (2022). Polycentric environmental governance to achieving SDG 16: Evidence from Southeast Asia and Eastern Africa. Forest, vol. 13. Available at https://doi.org/10.3390/f13010068
- Arnell, N. and S. Gosling. (2016). The impacts of climate change on river flood risk at the global scale. Climatic Change, vol. 134, pp. 387-401. Available at https:// doi.org/10.1007/s10584-014-1084-5
- Asariotis, R. (2020). Climate Change Impacts and Adaptation for Coastal Transportation Infrastructure: A Sustainable Development Challenge for SIDS in the Caribbean and Beyond. In Coastal and Marine Environments. Available at https://www.taylorfrancis. com/chapters/edit/10.1201/9780429441004-29/ climate-change-impacts-adaptation-coastaltransportation-infrastructure-sustainabledevelopment-challenge-sids-caribbean-beyondregina-asariotis
- Asariotis, R. (2021). Climate change impacts on seaports: A growing threat to sustainable trade and development. UNCTAD Prosperity for All. Available at https://unctad.org/news/climate-change-impactsseaports-growing-threat-sustainable-trade-anddevelopment
- Asian Development Bank. (2020a). Multihazard Risk Atlas of Maldives: Summary-Volume V. Manila. Available at https://www.adb.org/sites/default/files/ publication/601286/maldives-multihazard-risk-atlasvol5 4.pdf
- Asian Development Bank. (2020b). A Brighter Future for Maldives Powered by Renewables: Road Map for the Energy Sector 2020-2030. Available at https://www. adb.org/publications/renewables-roadmap-energysector-maldives
- Benton, T., C. Bieg, H. Harwatt, R. Pudasaini and L. Wellesley. (2021). Food System Impacts on Biodiversity Loss. Three Levers for Food System Transformation in Support of Nature. London: Chatham House, The Royal Institute of International Affairs. Available at https://www.unep.org/resources/

- publication/food-system-impacts-biodiversity-loss
- Brahic, C. (2005). Hotter Sahara could mean more rain for Sahel. SciDevNet. Available at https://www.scidev. net/global/news/hotter-sahara-could-mean-morerain-for-sahel/
- Carneiro, E., W. Lopes and G. Espindola. (2021). Linking urban sprawl and surface urban heat island in the Teresina-Timon conurbation area in Brazil. Land, vol. 10, no. 516. Available at https://doi.org/10.3390/ land10050516
- CARTO. (n.d.). Agenda2030 Teresina. Available at https:// agenda2030.carto.com/me
- Chen, G., A. Jain and S. Stolp. (2023). Why the Maldives 5 MW solar project is a game changer. World Bank Blogs. Available at https://blogs.worldbank.org/ endpovertyinsouthasia/why-maldives-5-mw-solarproject-game-changer
- Climate-ADAPT. (2022). Climate-ADAPT. Establishment of Early Warning Systems. Available at https://climateadapt.eea.europa.eu/en/metadata/adaptationoptions/establishment-of-early-warning-systems
- Dasgupta, S., N. Van Maanen, S. Gosling, F. Piontek, C. Otto and C.-F. Schleussner. (2021). Effects of climate change on combined labour productivity and supply: An empirical, multi-model study. The Lancet Planetary Health, vol. 5. Available at https://doi.org/10.1016/ \$2542-5196(21)00170-4
- Eccles, R., H. Zhang and D. Hamilton. (2019). A review of the effects of climate change on riverine flooding in subtropical and tropical regions. Journal of Water and Climate Change, vol. 10. Available at https://doi. org/10.2166/wcc.2019.175
- Economist Intelligence Unit. (2022). Energy transition will move slowly over the next decade. Available https://www.eiu.com/n/energy-transition-willmove-slowly-over-the-next-decade/#:~:text=EIU%20 forecasts%20that%2C%20despite%20the,slightly%20 from%2081%25%20in%202022
- Espindola, G., E. Neves da Costa C. and A. Cardoso Façanha. (2017). Four decades of urban sprawl and population growth in Teresina, Brazil. Applied Geography, vol. 79, pp. 73-83. Available at https://doi. org/10.1016/j.apgeog.2016.12.018
- Euroclima. (2022). The city of Teresina concludes the implementation of the "Mobility Observatory" project. Available at https://www.euroclima.org/en/recentevents-urban/news-urban/1644-the-city-of-teresinaconcludes-the-implementation-of-the-mobilityobservatory-project
- European Commission. (2020). Climate change, river flooding and adaptation. Available at https://

- files/2020-09/05_pesetaiv_river_floods_sc_ august2020_en.pdf
- European Commission. (2022). Large Scale Integrated Sea-level and Coastal Assessment Tool. Joint Research Centre Data Catalogue. Available at https:// data.irc.ec.europa.eu/collection/LISCOAST
- Ezguiaga Arguitectura, Sociedad y Territorio S.L. (2015). The Experience of Latin America and the Caribbean in Urbanization: Knowledge Sharing Forum on Development Experiences: Comparative Experiences of Korea and Latin America and the Caribbean. Discussion Paper IDB-DP-395. Inter-American Development Bank. Available at https://publications. iadb.org/en/experience-latin-america-andcaribbean-urbanization-knowledge-sharing-forumdevelopment-experiences
- FAO. (2014). FAO Statistical Yearbook. Africa Food and Agriculture. Accra. Available at https://www.fao. Hettiarachchi, S., C. Wasko and A. Sharma. (n.d.). org/3/i3620e/i3620e.pdf
- FAO. (2022a). Suite of Food Security Indicators. FAOSTAT. Available at https://www.fao.org/faostat/en/#data/ FS
- FAO. (2022b). Sustainable Development Goals. Indicator 6.4.1 - Change in water use efficiency over time. Available at https://www.fao.org/ sustainable-development-goals/indicators/641/ en/#:~:text=SDG%20Target%206.4.-,Target%20 6.4,people%20suffering%20from%20water%20 scarcity
- FAO. (n.d.a). Drought. Land & Water. Available at https:// www.fao.org/land-water/water/drought/en/
- FAO. (n.d.b). FAO Remote Sensing Survey reveals Tropical rainforests under pressure as agricultural expansion drives global deforestation. Available at https://www. fao.org/3/cb7449en/cb7449en.pdf
- FAO. (n.d.c). Sustainable Development Goals. Indicator 2.1.2 Prevalence of moderate or severe food insecurity in the population, based on the Food Insecurity Experience Scale. Available at https:// www.fao.org/sustainable-development-goals/ indicators/212/en/
- FAO. (n.d.d). Sustainable Development Goals. Indicator 15.2.1 - Progress towards sustainable forest management. Available at https://www.fao.org/ sustainable-development-goals/indicators/1521/en
- FAO and UN-Water. (2021). Progress on Level of Water Stress. Global Status and Acceleration Needs for SDG Indicator 6.4.2. Rome. Available at https://www.fao. org/3/cb6241en/cb6241en.pdf
- Feller, G. (2019). Investment flows into Jamaica Will the Kingston's Container Terminal upgrade help? Ajot Insights. Available at https://www.ajot.com/ insights/full/ai-investment-flows-into-jamaica-willthe-kingstons-container-terminal-upgrade-help

- joint-research-centre.ec.europa.eu/system/ Goffner, D., H. Sinare and L. Gordon. (2019). The Great Green Wall for the Sahara and the Sahel Initiative as an opportunity to enhance resilience in Sahelian landscapes and livelihoods. Regional Environmental Change, vol. 19, pp. 1417-1428. Available at https:// doi.org/10.1007/s10113-019-01481-z
 - Government of Saint Lucia. (2018). Saint Lucia's National Adaptation Plan (NAP) 2018-2028. Department of Sustainable Development, Ministry of Education, Innovation, Gender Relations and Sustainable Development. Available at https://www4.unfccc. int/sites/NAPC/Documents/Parties/SLU-NAP-May-2018.pdf
 - Hallegatte, S., J. Rentschler and J. Rozenberg. (2019). Lifelines: The Resilient Infrastructure Opportunity. Washington, D.C.: World Bank. Available at https:// openknowledge.worldbank.org/entities/publication/ c3a753a6-2310-501b-a37e-5dcab3e96a0b
 - Increase in flood risk resulting from climate change in a developed urban watershed - The role of storm temporal patterns. Hydrology and Earth System Sciences, vol. 22, pp. 2041–2056. Available at https:// doi.org/10.5194/hess-22-2041-2018
 - ILO. (2019). Working on a Warmer Planet. The Impact of Heat Stress on Labour Productivity and Decent Work. Executive Summary. Available at https://www.ilo.org/ wcmsp5/groups/public/---dgreports/---dcomm/--publ/documents/publication/wcms_712011.pdf
 - ILO. (2021). Fewer women than men will regain employment during the COVID-19 recovery says ILO. Gender Equality. Available at https://www. ilo.org/global/about-the-ilo/newsroom/news/ WCMS_813449/lang--en/index.htm
 - ILO. (2023). Data. ILOSTAT. Available at https://ilostat.ilo. org/data/
 - Internal Displacement Monitoring Centre. (2023). 2023 Global Report on Internal Displacement. Available at https://www.internal-displacement.org/globalreport/grid2023/
 - Internal Displacement Monitoring Centre. (2023). Global Internal Displacement Database. Available at https://www.internal-displacement.org/database/ displacement-data
 - Internal Displacement Monitoring Centre (IDMC). (2023). How We Monitor. Global Internal Displacement Database. Available at https://www.internaldisplacement.org/monitoring-tools
 - International Energy Agency. (2018). The Future of Cooling Opportunities for Energy-Efficient Air Conditioning. Available at https://www.iea.org/reports/the-futureof-cooling
 - International Energy Agency. (2022). Buildings. Paris. Available at https://www.iea.org/reports/buildings

- International Energy Agency. (2023). Data and statistics. Data and Statistics. Available at https://www.iea.org/ data-and-statistics
- International Monetary Fund. (2022). Climate change. Fossil fuel subsidies. Available at https://www.imf. org/en/Topics/climate-change/energy-subsidies
- IPBES. (2019). IPBES Global Assessment Preview. Introducing IPBES' 2019 Global Assessment Report on Biodiversity and Ecosystem Services: First global biodiversity assessment since 2005. Media Release. Available at https://www.ipbes.net/news/ipbes- global-assessment-preview
- IPBES. (2021). IPBES-IPCC Co-Sponsored Workshop Report on Biodiversity and Climate Change. Intergovernmental Science-Policy Platform on Biodiversity and Ecosystem Services. Intergovernmental Panel on Climate Change. Available at https://www.ipbes.net/sites/default/ files/2021-06/20210609_workshop_report_ embargo_3pm_CEST_10_june_0.pdf
- IPCC. (2014). AR5 Climate Change 2014: Impacts, Adaptation, and Vulnerability. Cambridge, United Kingdom and New York, USA: IPCC. Available at ITF. (2019). ITF Transport Outlook 2019. Paris: https://www.ipcc.ch/report/ar5/wg2/
- IPCC. (2019a). Framing and Context of the Report. In IPCC Special Report on the Ocean and Cryosphere in a Changing Climate, pp. 73-129. Available at https:// www.ipcc.ch/srocc/chapter/chapter-1-framing-andcontext-of-the-report/
- IPCC. (2019b). Land degradation. Chapter 4. In Special Report on Climate Change and Land. Available at Izaguirre, C., I. Losada, P. Camus, J. Vigh and V. Stenek. https://www.ipcc.ch/srccl/chapter/chapter-4/
- IPCC. (2021a). Climate Change 2021: The Physical Science Basis. Contribution of Working Group I to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change. United Kingdom of Great Britain and Northern Ireland; New York, USA: Intergovernmental Panel on Climate Change. Available at https://www. ipcc.ch/report/sixth-assessment-report-workinggroup-i/
- IPCC. (2021b). Future Global Climate: Scenario-based Projections and Near-term Information. In Climate Change 2021: The Physical Science Basis. Contribution of Working Group I to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change, pp. 553-672. Cambridge, United Kingdom of Great Britain and Northern Ireland; New York, USA: Cambridge University Press. Available at https:// www.ipcc.ch/report/ar6/wg1/downloads/report/ IPCC_AR6_WGI_Chapter04.pdf
- IPCC. (2021c). Weather and Climate Extreme Events in a Changing Climate. In Climate Change 2021: The Physical Science Basis. Contribution of Working Group I. In Sixth Assessment Report of the Intergovernmental Panel on Climate Change. Cambridge, United Kingdom of Great Britain and New York, USA. Available at

- https://www.ipcc.ch/report/ar6/wg1/downloads/ report/IPCC_AR6_WGI_Chapter11.pdf
- IPCC. (2022). Climate Change 2022: Impacts, Adaptation and Vulnerability. Contribution of Working Group II to the Sixth Assessment Report of the Intergovernmental Panel on Climate Change. Cambridge, United Kingdom of Great Britain and Northern Ireland; New York, USA: Cambridge University Press. Available at https:// report.ipcc.ch/ar6/wg2/IPCC_AR6_WGII_FullReport.
- IPCC. (2023). AR6 Synthesis Report: Climate Change 2023. Switzerland. Available at https://www.ipcc.ch/ report/sixth-assessment-report-cycle/
- IPCC. (n.d.a). FAQ 4: 4. How are people adapting to the effects of climate change and what are the known limits to adaptation? IPCC Sixth Assessment Report. Impacts. Adaptation and Vulnerability. Available https://www.ipcc.ch/report/ar6/wg2/about/ frequently-asked-questions/keyfaq4/
- IPCC. (n.d.b). IPCC WGI Interactive Atlas. IPCC Working Group I (WGI): Sixth Assessment Report. Available at https://interactive-atlas.ipcc.ch
- Organisation for Economic Co-Operation and Development. Available at https://www.oecd-ilibrary. org/transport/itf-transport-outlook-2019_transp_ outlook-en-2019-en
- IUCN. (2023). The IUCN Red List of Threatened Species. The IUCN Red List of Threatened Species. Version 2022-2. Available at https://www.iucnredlist.org
- (2020). Climate change risk to global port operations. Nature Climate Change, vol. 11. Available at https:// doi.org/10.1038/s41558-020-00937-z
- Lloyd's List. (2022). One Hundred Ports. 2022. Lloyd's List. Available at https://lloydslist.maritimeintelligence. informa.com/one-hundred-container-ports-2022
- Lowe, R., S. Rvan, R. Mahon, C. Van Meerbeeck, A. Trotman and L.-L. Boodram. (2020). Building resilience to mosquito-borne diseases in the Caribbean. Available at https://doi.org/10.1371/journal.pbio.3000791
- Luo, T. (2015). Agueduct Global Flood Risk Maps. World Resources Institute. Data Set. Available at https:// www.wri.org/data/agueduct-global-flood-risk-maps
- Lyons, K. (2022). How to move a country: Fiji's radical plan to escape rising sea levels. Guardian. Available at https://www.theguardian.com/environment/2022/ nov/08/how-to-move-a-country-fiji-radical-planescape-rising-seas-climate-crisis#:~:text=At%20 present%2C%2042%20Fijian%20villages,being%20 added%20to%20the%20list
- Ministry of Environment, Climate Change and Technology. Republic of Maldives. (2022a). List of protected areas. Available at https://www.environment.gov.mv/ v2/en/download/11475

- Ministry of Environment, Climate Change and Technology. Republic of Maldives. (2022b). Maldives re-opens tender for 40 MWh Battery Energy Storage System (BESS) Project. Available at https://www. environment.gov.mv/v2/en/news/16082
- Ministry of Fisheries, Marine Resources and Agriculture. (2019). Fisheries Act of the Maldives. Act No. 14/2019. Available at https://faolex.fao.org/docs/ pdf/mdv195984.pdf
- Monioudi, I., R. Asariotis, A. Becker, C. Bhat and others. (2018). Climate change impacts on critical international transportation assets of Caribbean small island developing States (SIDS): The case of Jamaica and Saint Lucia. Regional Environmental Change, vol. 18, pp. 2211-2225. Available at https:// link.springer.com/article/10.1007/s10113-018-1360-4
- Moore, J., A. Mascarenhas, J. Bain and S. Straus. (2017). Developing a comprehensive definition of sustainability. Implementation Science, vol. 12. Available at https://doi.org/10.1186/s13012-017-
- National Geospatial-Intelligence Agency. (2019). World Port Index. Maritime Safety Information. Nautical Publications. Available at https://msi.nga.mil/ Publications/WPI
- Niang, I., O. Ruppel, M. Abdrabo, A. Essel, C. Lennard, J. Padgham and P. Urguhart. (2014). Chapter 22 Africa. In Climate Change 2014: Impacts, Adaptation, and Vulnerability. Part B: Regional Aspects. Contribution of Working Group II to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change, pp. 1199-1265. Cambridge, United Kingdom of Great Britain and Northern Ireland; New York, USA: Cambridge University Press. Available at https:// www.researchgate.net/publication/309475977_ Chapter_22_Africa_In_Climate_Change_2014_ Impacts_Adaptation_and_Vulnerability_Part_B_ Regional_Aspects_Contribution_of_Working_ Group_II_to_the_Fifth_Assessment_Report_of_the_ Intergovernmental_Panel_on_
- Notteboom, Theo, Athanasios Pallis and Jean-Paul Rodrigue. (2019). Risk of Hurricanes for Global Container Ports, 2019. Port Economics, Management and Policy. A Comprehensive Analysis of the Port Industry, pp. 690. Available at https:// porteconomicsmanagement.org/pemp/contents/ part6/port-resilience/hurricanes-global-containerports/
- NRDC. (2022). Expanding Heat Resilience Across India: Heat Action Plan Highlights 2022.
- Available at https://www.nrdc.org/sites/default/files/ india-heat-resilience-20220406.pdf
- OECD, World Bank and UN Environment. (2018). Financing Climate Futures. Rethinking Infrastructure. Policy Highlights. Paris: OECD Publishing. Available at https://www.oecd.org/environment/cc/climate-

- futures/policy-highlights-financing-climate-futures.
- Opitz-Stapleton, S., R. Nadin, J. Kellet, M. Calderone, A. Quevedo, K. Peters and L. Mayhew. (2019). Riskinformed development. From crisis to resilience. USA. United Nations Development Programme. Available at https://cdn.odi.org/media/documents/12711.pdf
- Ostrom, E. (2010). Polycentric systems for coping with collective action and global environmental change. Global Environmental Change, vol. 10, pp. 550-557. Available at https://doi.org/10.1016/j. gloenvcha.2010.07.004
- Parra, I. (2022, April). A warm mission to recommend actions for resilience and sustainability. United Nations Habitat. Urban Resilience Hub. Available at https://urbanresiliencehub.org/a-warm-missionto-recommend-actions-for-resilience-andsustainability/
- Pate, D. (2022). St Lucia signs 30-year deal for its port development. Our Today. Available at https://our. today/st-lucia-signs-30-year-deal-for-its-portdevelopment/
- Pausata, F., M. Gaetini, G. Messori, A. Berg, D.M. de Souza, R. Sage and P. deMenocal. (2020). The greening of the Sahara: Past Changes and Future Implications. One Earth, vol. 2, no. 3, pp. 235-250. Available at https:// doi.org/10.1016/j.oneear.2020.03.002
- PSM News. (2023). Customs destroys over 500,000 plastic bags. Press Release. Available at https:// psmnews.mv/en/118930
- Ridgwell, A., M. Maslin and A. Watson. (2022). Reduced effectiveness of terrestrial carbon sequestration due to an antagonistic response of ocean productivity. Geophysical Research Letters, vol. 29, no. 6, pp. 19-1-19-4. Available at https://doi. org/10.1029/2001GL014304
- Rogers, D. and V. Tsirkunov. (2011). Global Assessment Report on Disaster Risk Reduction, 2011. Costs and Benefits of Early Warning Systems. United Nations International Strategy for Disaster Reduction and World Bank. Available at https://www.preventionweb. net/english/hyogo/gar/2011/en/badocs/Rogers_&_ Tsirkunov_2011.pdf
- Saley, I., S. Salack, I. Sanda, M. Moussa, A. Bonkaney, M. Ly and M. Fodé. (2019). The possible role of the Sahel Greenbelt on the occurrence of climate extremes over the West African Sahel. Atmospheric Science Letters, vol. 20, no. 8. Available at https://doi.org/10.1002/ asl 927
- Statista. (2023). Latin America & Caribbean: Urbanization from 2011 to 2021. Available at https://www. statista.com/statistics/699089/urbanization-in-latinamerica-and-caribbean/
- Strauss, B., P. Orton, K. Bittermann, M. Buchanan, D. Gilford, R. Kopp, S. Kulp, C. Massey, H. de Moel

- from Hurricane Sandy attributable to sea level rise caused by anthropogenic climate change. Nature Communications, vol. 12. Available at https://doi. org/10.1038/s41467-021-22838-1
- Strunsky, S. (2013). Port Authority puts Sandy damage at \$2.2 billion, authorizes \$50 million to power wash PATH tunnels. NJ. Available at https://www.nj.com/ UN Habitat. (2021). Housing, slums and informal news/2013/10/port_authority_sandy_22billion_ outlines_recovery_measures.html
- Sultan, B. and M. Gaetani. (2016). Agriculture in West Africa in the Twenty-First Century: Climate Change and Impacts Scenarios, and Potential for Adaptation. Frontier in Plant Science 7:1262, vol. 7, no. 1262. Available at https://doi.org/10.3389/fpls.2016.01262
- Tellman, B., J.A. Sullivan, C. Kuhn, A.J. Kettner, C.S. Doyle, UN Women. (2021b). Women and Girls Left Behind. G.R. Brakenridge, T.A. Erickson and D.A. Slayback. (2021). Satellite imaging reveals increased proportion of population exposed to floods. Nature, vol. 590, pp. 80-86. Available at https://www.nature.com/articles/ s41586-021-03695-w
- The Statistics Division of the United Nations Department of Economic and Social Affairs. (2022). 13 Climate Action. The Sustainable Development Goals. Extended Report 2022. The Statistics Division of the United Nations Department of Economic and Social Affairs. Available at https://unstats.un.org/sdgs/report/2022/ extended-report/Extended-Report_Goal-13.pdf
- The World Bank. (2022). What You Need to Know About Food Security and Climate Change. Available at https://www.worldbank.org/en/news/ feature/2022/10/17/what-you-need-to-know-aboutfood-security-and-climate-change
- Turmena, L. and F. Maia. (2022). City Profiles No. 5 Teresina, Brazil. Transformative Urban Coalitions. Bonn: United Nations University, Institute for Environment and Humans Security. Available http://collections.unu.edu/eserv/UNU:8994/ n20221117_TUC_City_Profile_Teresina.pdf
- Uchoa, G. (n.d.). Innovation for Urban Resilience. Teresina, Brazil. Municipality of Teresina. Available at http:// capacitybuildingunhabitat.org/wp-content/uploads/ news_items/un-habitat-hosts-event-on-innovativetools-for-citizen-consultation-in-latin-america/2019_ Teresina2030_SCWEC.pdf
- UN Data. (2023). UN Data. Explorer. Available at http:// data.un.org/Explorer.aspx?d=EDATA
- UN DESA. (2018). World Urbanization Prospects 2018. United Nations. Department of Economic and Social Affairs. Population Dynamics. Available at https:// UNDP Global Centre for Public Service Excellence. population.un.org/wup/
- UN DESA. (2022). The Sustainable Development Goals Report 2022. United Nations. Department of Economic and Social Affairs. Available at https:// unstats.un.org/sdgs/report/2022/The-Sustainable-Development-Goals-Report-2022.pdf

- and S. Vinogradov. (2021). Economic damages UN DESA. (2023a). SDG Indicators. Metadata repository. Sustainable Development Goals. Available at https:// unstats.un.org/sdgs/metadata/
 - UN DESA. (2023b). The Sustainable Development Goals Report 2023. New York, USA: United Nations. Department of Economic and Social Affairs. Forthcoming.
 - settlements. UN Habitat. Urban Indicators Database. Available at https://data.unhabitat.org/pages/ housing-slums-and-informal-settlements
 - UN Women. (2021a). Measuring the shadow pandemic: Violence against women during COVID-19. UN Women. Available at https://data.unwomen.org/ publications/vaw-rga
 - Glaring Gaps in Pandemic Responses. UN Women. Available at https://data.unwomen.org/sites/ default/files/documents/Publications/glaring-gapsresponse-RGA.pdf
 - UNCTAD. (2017a). Climate Change Impacts on Coastal Transport Infrastructure in the Caribbean: Enhancing the Adaptive Capacity of Small Island Developing States (SIDS), Jamaica: A Case Study. UNDA Project 14150. Available at https://www.preventionweb. net/publication/climate-change-impacts-coastaltransport-infrastructure-caribbean-enhancingadaptive
 - UNCTAD. (2017b). Climate Change Impacts on Coastal Transport Infrastructure in the Caribbean: Enhancing the Adaptive Capacity of Small Island Developing States (SIDS), Saint Lucia: A Case Study. UNDA Project 14150. Available at https://unctad.org/system/files/ official-document/dtltlb2018d3_en.pdf
 - UNDP. (2022a). A Holistic Approach to Addressing Water, Resources Challenges in Yemen. UNDP Strategic Framework. Available at https://www.undp.org/ sites/g/files/zskgke326/files/2022-11/2022%20 Nov%20Water%20Resources%20Challenges%20 in%20Yemen.pdf
 - UNDP. (2022b). Assessing COVID-19 impact on the Sustainable Development Goals. Data Futures Platform. Available at https://data.undp.org/content/ assessing-covid-impacts-on-the-sdgs/
 - UNDP Climate. (2022). On tap: How the Maldives is restoring water security on its most vulnerable outer islands. Available at https://undp-climate.exposure. co/on-tap-how-the-maldives-is-restoring-watersecurity-on-its-most-vulnerable-outer-islands
 - (2018). Foresight Manual. Empowered Futures for the 2030 Agenda. Available at https://www.undp.org/ sites/g/files/zskgke326/files/publications/UNDP_ ForesightManual_2018.pdf
 - UNDRR. (2019). Disaster Risk Reduction in the Republic of Fiji. Status Report 2019. Bangkok.

- Available at https://www.preventionweb.net/ files/68251_682302fijirevised16oct2019. p d f ? _ q l = 1 * 1 v g u c 7 i * _ ga*MTI2NDY0MDAyMS4xNjgyNjY0MzY4*_ g a _ D 8 G 5 W X P 6 Y M * M TY4MzYzNDE3NC4xMS4xLjE20DM 2MzQxODUuMC4wLjA
- UNDRR. (2021). Global Assessment Report on Disaster Risk Reduction. Special Report on Drought 2021. Available at https://www.undrr.org/publication/garspecial-report-drought-2021
- UNDRR. (2022a). Global Status of Multi-Hazard Early Warning Systems: Target G. Bonn. Available at https:// www.undrr.org/publication/global-status-multihazard-early-warning-systems-target-g
- UNDRR. (2022b). Monitoring Sendai Framework. Available at https://www.undrr.org/monitoringsendai-framework
- UNDRR. (2023). Early Warnings For All Initiative scaled up into action on the ground. Press Releases. Available at https://www.undrr.org/news/early-warnings-allinitiative-scaled-action-ground
- UNDRR. (n.d.a). Disaster risk. Sendai Framework Terminology on Disaster Risk Reduction. Available at https://www.undrr.org/terminology/disaster-risk
- UNDRR. (n.d.b). Risk Information Exchange. Risk Information Exchange. Available at https://rix.undrr. org
- UNEP. (2021). Progress on Integrated Water Resources Management. Tracking SDG 6 Series: Global Indicator 6.5.1 Updates and Acceleration Needs. United Nations Environment Programme. Available at https://www.unwater.org/sites/default/files/app/ uploads/2021/09/SDG6_Indicator_Report_651_ Progress-on-Integrated-Water-Resources-Management_2021_EN.pdf
- UNESCO. (2019). Global Education Monitoring Report. Migration, Displacement & Education: building bridges, not walls. Paris. Available at https://www.unesco.org/ gem-report/en/migration
- UN-Habitat. (2021a). UN-Habitat promotes urban resilience projects to support sustainability. Available https://unhabitat.org/news/13-aug-2021/unhabitat-promotes-urban-resilience-projects-tosupport-sustainability
- UN-Habitat. (2021b). Urban Resilience Diagnosis: Teresina. Nairobi. Available at https://urbanresiliencehub.org/ wp-content/uploads/2021/04/Urban-Resilience-Diagnosis-Teresina.pdf
- UNHCR. (n.d.). Left Behind. Refugee education in crisis. Available at https://www.unhcr.org/left-behind/
- UNICEF. (2021). The Climate Crisis Is a Child Rights Crisis: Introducing the Children's Climate Risk Index. New York. Available at https://www.unicef.org/

- media/105531/file/UNICEF_climate%20crisis_child_ rights_crisis-summary.pdf
- United Nations. (2015a). Paris Agreement. Available at https://unfccc.int/sites/default/files/english_paris_ agreement.pdf
- United Nations. (2015b). Resolution adopted by the General Assembly on 3 June 2015, Sendai Framework for Disaster Risk Reduction 2015-2030. 23 June. A/RES/69/283. Available at https:// www.un.org/en/development/desa/population/ migration/generalassembly/docs/globalcompact/A_ RES_69_283.pdf
- United Nations. (2015c). Resolution adopted by the General Assembly on 25 September 2015, Transforming our World: The 2030 Agenda for Sustainable Development. 21 October. A/RES/70/1. Available at https://documents-dds-ny.un.org/ doc/UNDOC/GEN/N15/291/89/PDF/N1529189. pdf?OpenElement
- United Nations. (2019). Stressing Air Pollution Kills 7 million People Annually, Secretary-General Urges Governments to Build Green Economy, in Message for World Environment Day. United Nations Meetings Coverage and Press Releases. Available at https:// press.un.org/en/2019/sgsm19607.doc.htm
- United Nations. (2020). United Nations Common Guidance on Helping Build Resilient Societies. New York. Available at https://unsdg.un.org/resources/uncommon-guidance-helping-build-resilient-societies
- United Nations. (2022a). Key Messages. The Sustainable Development Goals Report 2022. Available at https:// unstats.un.org/sdgs/files/report/2022/SDGs_ Report_Key_Messages_2022.pdf
- United Nations. (2022b). World Population Prospects 2022. UN Department of Economic and Social Affairs Population Division. Available at https://population. un.org/wpp/
- United Nations. (2023a). Statistics. SDG Indicators Database. Department of Economic and Social Affairs. Available at https://unstats.un.org/sdgs/ dataportal/database
- United Nations. (2023b). With highest number of violent conflicts since Second World War, United Nations must rethink efforts to achieve, sustain peace, speakers tell Security Council. Meetings Coverage and Press Releases. Available at https://press.un.org/ en/2023/sc15184.doc.htm
- United Nations. (n.d.a). 4 Quality Education. Sustainable Development Goals. Available at https://www.un.org/ sustainabledevelopment/education/
- United Nations. (n.d.b). Transforming our world: the 2030 Agenda for Sustainable Development. United Nations. Department of Economic and Social Affairs Sustainable Development. Available at https://sdgs. un.org/2030agenda

- United Nations Conference on Trade and Development. (2022a). Review of Maritime Transport 2022. Navigating Stormy Waters. Geneva: United Nations. Available at https://unctad.org/system/files/official-document/rmt2022_en.pdf
- United Nations Conference on Trade and Development. (2022b). Policy Brief. No.103. Climate-resilience of seaports: Adequate finance is critical for developing countries but remains a major challenge. United Nations Conference on Trade and Development. Available at https://unctad.org/system/files/official-document/presspb2022d11_en.pdf
- United Nations Statistics Division. (2022). Energy Statistics Database 2020: Notes on Sources. Energy Statistics Section. New York, USA: Available at https://unstats.un.org/unsd/energystats/pubs/yearbook/2020/metadata.pdf
- UN-Water. (n.d.). Progress on Drinking Water (SDG Target 6.1). Available at https://sdg6data.org/en/indicator/6.1.1
- van Vuuren, D., J. Edmonds, M. Kainuma, K. Riahi, A. Thomson, K. Hibbard, G. Hurtt, T. Kram, V. Krey, J.-F. Lamarque, T. Masui, M. Meinshausen, N. Nakicenovic, S. Smith and S. Rose. (2011). The representative concentration pathways: an overview. *Climatic Change*, vol. 109. Available at https://doi.org/10.1007/s10584-011-0148-z
- Verschuur, J., E. Koks and J. Hall. (2022). Ports' criticality in international trade and global supply-chains. *Nature Communications*, vol. 13, no. 4351. Available at https://doi.org/10.1038/s41467-022-32070-0
- Verschuur, J., E. Koks, S. Li and J. Hall. (2023). Multihazard risk to global port infrastructure and resulting trade and logistics losses. *Communications Earth* & *Environment*, vol. 4, no. 5. Available at https://doi. org/10.1038/s43247-022-00656-7
- Vousdoukas, M., L. Mentaschi, E. Voukouvalas, M. Verlaan, S. Jevrejeva, L. Jackson and L. Feyen. (2018). Global probabilistic projections of extreme sea levels show intensification of coastal flood hazard. *Nature Communications*, vol. 9. Available at https://doi.org/10.1038/s41467-018-04692-w
- Ward, P., F. Sperna, A. Bouwman and B. Jongman. (2013). Assessing flood risk at the global scale: Model setup, results, and sensitivity. *Environmental Research Letters*, vol. 8. Available at https://doi.org/10.1088/1748-9326/8/4/044019
- WFP. (n.d.). A global food crisis. Available at https://www.wfp.org/global-hunger-crisis
- WHO. (2022, November). Household air pollution. Household Air Pollution. Available at https://www.who.int/news-room/fact-sheets/detail/household-air-pollution-and-health
- WHO. (2023). World Health Statistics 2023. Monitoring Health for the SDGs. Available at https://www.who.

- int/data/gho/publications/world-health-statistics
- WHO. (2023a). SDG Indicator 11.6.2 Concentrations of fine particulate matter (PM2.5). The Global Health Observatory. Available at https://www.who.int/data/gho/data/indicators/indicator-details/GHO/concentrations-of-fine-particulate-matter-(pm2-5)
- WHO. (2023b). The Global Health Observatory. Indicators. Available at https://www.who.int/data/gho/data/indicators/indicator-details/
- WHO. (n.d.a). Air quality and health. Available at https://www.who.int/teams/environment-climate-change-and-health/air-quality-and-health/sectoral-interventions/health-care-activities/strategies
- WHO. (n.d.b). Drought. Drought. Available at https://www.who.int/health-topics/drought#tab=tab_1
- WMO. (2018). *Multi-Hazard Early Warning Systems:* A Checklist. Geneva: World Meteorological Organization. Available at https://library.wmo.int/doc_num.php?explnum_id=4463
- WMO. (2021). WMO Atlas of Mortality and Economic Losses from Weather, Climate and Water Extremes (1970–2019). WMO-No.1267. Geneva. Available at https://library.wmo.int/index.php?lvl=notice_display&id=21930#.ZGSyzy8Rpm_
- WMO. (2023). Early Warnings For All Initiative scaled up into action on the ground. Available at https://public.wmo.int/en/media/press-release/early-warnings-all-initiative-scaled-action-ground#:~:text=The%20 Early%20Warnings%20For%20All%20Initiative%20 (EW4All)%20was%20formally%20launched,by%20 the%20end%20of%202027
- World Bank. (2018). Missed Opportunities: The High Cost of Not Educating Girls. Available at https://www.worldbank.org/en/topic/education/publication/missed-opportunities-the-high-cost-of-not-educating-girls#:~:text=The%20report%20says%20that%20limited,primary%20education%20is%20not%20enough
- World Bank. (2019). Maldives Ventures into the Blue Economy. Available at https://www.worldbank.org/en/news/feature/2019/07/11/maldives-ventures-into-the-tlue-economy
- World Bank. (2022a). Poverty and Shared Prosperity 2022. Correcting Course. Washington, D.C. Available at https://www.worldbank.org/en/publication/poverty-and-shared-prosperity
- World Bank. (2022b). Poverty. Overview. Available at https://www.worldbank.org/en/topic/poverty/overview
- World Bank. (2023). The World Bank In Maldives. Available at https://www.worldbank.org/en/country/maldives/overview
- World Bank Group. (2017). Future of Food. Shaping the Food System to Deliver Jobs. Washington, D.C. Available at https://documents1.worldbank.org/

- curated/en/406511492528621198/pdf/114394-WP-PUBLIC-18-4-2017-10-56-45-ShapingtheFoodSystem toDeliverJobs.pdf
- World Bank Group. (2021). Fiji. Climate Change Knowledge Portal for Development Practitioners and Policy Makers. Available at https://climateknowledgeportal. worldbank.org/country/fiji/vulnerability
- World Economic Forum. (2021a). It will take another 136 years to close the global gender gap. Gender Inequality. Available at https://www.weforum.org/agenda/2021/04/136-years-is-the-estimated-journey-time-to-gender-equality/
- World Economic Forum. (2021b). *Global Gender Gap Report 2021: Insight Report*. Available at https://www3.weforum.org/docs/WEF_GGGR_2021.pdf
- World Trade Organization. (2023). A Year of Turbulence on Food and Fertilizers Markets. Trade Monitoring Updates. Available at https://www.wto.org/english/news_e/news23_e/trdev_02mar23_e.pdf
- Yosef, G., R. Walko, R. Avisar, F. Tatarinov, E. Rotenberg and D. Yakir. (2018). Large-scale semi-arid afforestation can enhance precipitation and carbon sequestration potential. *Scientific Reports*, vol. 8, no. 996. Available at https://doi.org/10.1038/s41598-018-19265-6
- Zachos, J., G. Dickens and R. Zeebe. (2008). An early Cenozoic perspective on greenhouse warming and carbon-cycle dynamics. *Nature*, vol. 451, pp. 279–283. Available at https://doi.org/10.1038/nature06588
- Zeng, Z., J. Zhan, L. Chen, H. Chen and S. Cheng. (2021). Global, regional, and national dengue burden from 1990 to 2017: A systematic analysis based on the global burden of disease study 2017. *EClinicalMedicine*, vol. 32, no. 100712. Available at https://doi.org/10.1016/j.eclinm.2020.100712

